

SOUTHBOUND

ITEM DETAIL SUMMARY SHEET FOR SPRINGFIELD - HARTFORD IR 091-1(20)

SOUTHBOUND

MILE MARKER	MILE MARKER	POS.	SOLID ROCK EXCAV.	COMM. EXCAV.	TRENCH EXCAV.		EARTH BORROW	AGGREG. SURFACE COURSE	CLEAN. CULV. PIPE L.F.	CORRUGATED STEEL PIPE			REINFORCED CONCRETE PIPE			RELAY PIPE	6" UND.	CONC. CL B CY	REIN. STEEL LBS	GRATE TYPE EA	CHAN. ELEV EA	BIT. CONC. PAV'T.	SNOW FENCE	GUARDRAIL ITEMS		STONE FILL			GRAN-ULAR BORROW	SUBBASE OF CRUSHED GRAVEL	REMARKS
					EARTH CY	ROCK CY				D	L	TH	D	L	CL									621.80	621.75	TYPE I	TYPE II	TYPE III			
44.50	44.55	OUT.																													LEDGE SCALING AREA
44.57		OUT.							5												1										RAISE CURB DI
44.64		OUT.							5												1										RAISE CURB DI
44.96		OUT.							5												1										RAISE CURB DI
44.96		MED.							5												1										RAISE CURB DI
44.99		NB/SB																					240								INSTALL 60 L.F. OF SNOW FENCE ON EACH SIDE OF BRIDGES 29N & 29S AS PER TYPICAL FOR GALV. BOX BEAM RAIL. I-91 OVER T.H. #3
45.04	45.40	MED.																													ROCK DISPOSAL AREA
45.05		OUT.							5												1										RAISE CURB DI
45.10		OUT.							5												1										RAISE CURB DI
45.15		OUT.							5												1										RAISE CURB DI
45.17		OUT.							5												1										RAISE CURB DI
45.23		OUT.							5												1										RAISE CURB DI
45.27		OUT.							5												1										RAISE CURB DI
45.33		OUT.							5												1										RAISE CURB DI
46.24		MED.							5												1										RAISE CURB DI
46.29		MED.							5												1										RAISE CURB DI
46.34		MED.							5												1										RAISE CURB DI
46.46		MED.							5												1										RAISE CURB DI
47.05	47.25	OUT.																													LEDGE SCALING AREA.
47.49	47.63	OUT.																													LEDGE SCALING AREA.
47.55		OUT.				1.0			5																						RCDI COVERED BY ROCK SLIDE. EXPOSE & FLUSH DI. REHAB. OR REPLACE DI IF DAMAGED.
48.39		MED.				5	5	5																							REMOVE TREES IN VICINITY OF OUTLET, EXTEND PIPE 10' & FLATTEN SOUTH DITCH SLOPE TO 1-10 WITHIN THE 30' CLEAR ZONE OR AS PER RESIDENT ENGINEER. PAY AS THINNING AND TRIMMING.
48.48		MED.				5	5	5																							REMOVE TREES IN VICINITY OF OUTLET, EXTEND PIPE 10' & FLATTEN SOUTH DITCH SLOPE TO 1-10 WITHIN THE 30' CLEAR ZONE OR AS PER RESIDENT ENGINEER. PAY AS THINNING AND TRIMMING.
48.60		MED.							5												1										RAISE CURB DI
48.65		MED.							5												1										RAISE CURB DI
48.78		MED.							5												1										RAISE CURB DI
48.82		MED.				6.7			5																5.0						CLEAN OUTLET OF 12' ACCOMP. EXCAVATE DITCH @ OUTLET & PLACE STONE FILL, TYPE I IN DITCH.
48.89		MED.							5												1										RAISE CURB DI
SHEET TOTALS			-	-	17.7	10	10	-	105	-	-	-	-	-	-	-	-	-	-	-	19	-	240	-	-	5.0	-	-	-	-	

SURVEYED BY _____ DATE _____
DRAWN BY _____ DATE _____
SQUAD LEADER D.F. HALE
DESIGN FILE NO. ZFA2155.501 87A025.DGN
PRF FILE 87A025S08 DATE PLOTTED 31-JAN-1992
PROJ. NAME SPRINGFIELD-HARTFORD
PROJ. NO. IR 091-1(20)
SHEET 19 OF 133 SHEETS