

SOUTHBOUND

ITEM DETAIL SUMMARY SHEET FOR SPRINGFIELD - HARTFORD IR 091-1(20)

SOUTHBOUND

MILE MARKER	MILE MARKER	POS.	SOLID ROCK EXCAV.	COMM. EXCAV.	TRENCH	EXCAV.	EARTH BORROW	AGGREG. SURFACE COURSE	CLEAN. CULV. PIPE L.F.	CORRUGATED STEEL PIPE			REINFORCED CONCRETE PIPE			RELAY PIPE	6" UND.	CONC. CL. B CY	REIN. STEEL LBS	GRATE TYPE A EA	CHAN. ELEV EA	BIT. CONC. PAV'T.	SNOW FENCE	GUARDRAIL ITEMS		STONE FILL			GRAN-ULAR BORROW	SUBBASE OF CRUSHED GRAVEL	REMARKS
					EARTH CY	ROCK CY				D	L	TH	D	L	CL									621.80	621.75	TYPE I	TYPE II	TYPE III			
68.98		NB/SB																				200								INSTALL 50 L.F. OF SNOW FENCE ON EACH SIDE OF BRIDGES 41N & 41S AS PER TYPICAL FOR GALV. BOX BEAM RAIL. I-91 OVER RAMP C.	
69.16	69.19	OUT.																												REMOVE EXISTING TREATED TIMBER CURB AND CONSTRUCT 138 L.F. OF NEW TREATED TIMBER CURB. PAY AS: REMOVAL OF EXISTING CURB, ITEM 616.41 - 138 L.F. TREATED TIMBER CURB, ITEM 616.35 - 138 L.F.	
69.39	69.60	OUT.		660	300										800	1.0	20					570								LENGTHEN RAMP 'E' AS DESIGNATED ON PLANS. ADJUST DRAINAGE AS NECESSARY.	
69.81		NB/SB																					320							INSTALL 80 L.F. OF SNOW FENCE CONTINUOUSLY ON EACH SIDE OF BRIDGES 42N & 42S AS PER TYPICAL FOR GALV. BOX BEAM RAIL. I-91 OVER I-89.	
I-91/I-89	INTERCHANGE		2						10																					I-91/I-89 INTERCHANGE; REMOVE TOPS FROM ALL EXISTING THROAT DI'S AND REPLACE WITH GRATES, TYPE 'A'. PAY AS SOLID ROCK EXC., ITEM 203.16 FOR REMOVAL OF THROAT DI TOPS. FLUSH ANY PIPES THAT HAVE SILT DEPOSITS.	
SHEET TOTALS					2	660	300	-	-	-	10	-	-	-	-	800	1.0	20	6-A	6	570	520	-	-	-	-	-	-	-		

SURVEYED BY _____ DATE _____
 DRAWN BY _____ DATE _____
 SQUAD LEADER D.F. HALE
 DESIGN FILE NO. ZFA2H55.501 87A025.DGN
 PRF FILE 87A025S13 DATE PLOTTED 31-JAN-1992
 PROJ. NAME SPRINGFIELD-HARTFORD
 PROJ. NO. IR 091-1(20)
 SHEET 24 OF 133 SHEETS