STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EACH	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POST	FLANGED CHANNEL (LB / FT) 1.12	FLANGED CHANNEL (LB / FT) 2.00	FLANGED CHANNEL (LB / FT) 3.00	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (IN) 3.00 (LB / FT) 1.30	TUBULAR ALUMINUM Ø (IN) 4.00 (LB / FT) 1.70	TUBULAR ALUMINUM Ø (IN) 4.0 MOD (LB / FT) 1.70	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	W-SHAPE STEEL SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
OPTION ITEMS																																				
INSPECT 500+00 (8' RT)	DO NOT ENTER	1	36	36	9						2					30																	R5-1 SHSM		
INSPECT 500+00 (8' RT)	STOP	1	36	36	9						--																					R1-1 SHSM		
INSPECT 500+00 (8' RT)	ONE WAY	1	36	12	3						--																					R6-1R SHSM		
INSPECT 500+75 (8' RT)	WRONG WAY	1	36	24	6.00						2					30																	R5-1A SHSM		
INSPECT 500+75 (8' RT)	ONLY	1	24	30	5						--																					R3-5R SHSM		
INSPECT 500+75 (8' RT)	DO NOT BLOCK INTERSECTION	1	24	30	5						--																					R10-7 SHSM		
INSPECT 501+60 (5' RT)	ONE WAY	1	36	12	3						2					30																	R6-1R SHSM		
INSPECT 502+50 (10' RT)	M1	1	24	24	4						1					30																	RS-017 SHSM		
INSPECT 503+00 (5' RT)	ONE WAY	1	36	12	3						2					30																	R6-1R SHSM		
INSPECT 505+00 (5' RT)	ONE WAY	1	36	12	3						2					30																	R6-1R SHSM		
INSPECT 506+25 (5' RT)	ONE WAY	1	36	12	3						2					30																	R6-1R SHSM		
												FT .	FT .	FT .	FT .	FT 210 .	FT .	XXXXX XXXXX XXXXX XXXXX	EA .	LB .	LB .	LB .	EA.	LB .	LB .	LB .	LB .								
	TOTALS				SF 53.	SF .	EA. .	SF .	XXXXXXXXXX XXXXXXXXXX XXXXXXXXXX				FT .				FT 210.				LB .			EA.	LB .				EA. .	EA. .	LB .						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: **GUILFORD**
PROJECT NUMBER: **IM 091-1(25)**

FILE NAME: **D91A222TRF.DGN** PLOT DATE:
PROJECT MANAGER: **P. LIBBY** DRAWN BY: **P. BEYOR**
DESIGNED BY: **P. BEYOR** CHECKED **A. BOMBARDIER**
TRAFFIC SIGN SUMMARY SHEET #3 SHEET **42** OF **46**