

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
				ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	TEMPORARY DETOUR	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
				10						10		HR	BULLDOZER RENTAL, TYPE I	608.10	EST.	ITEM 613.10 - STONE FILL, TYPE I		
				10						10		HR	POWER GRADER RENTAL	608.15	EST.	9	CY	ROADWAY
				10						10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.	87	CY	STONE SLOPE, ABUTMENT 1
				10						10		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.	103	CY	STONE SLOPE, ABUTMENT 2
						0.5				0.5		MGAL	DUST CONTROL WITH WATER	609.10	0.2	199	CY	SUBTOTAL
						2				2		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	-	1	CY	ROUNDING
						200				200		CY	STONE FILL, TYPE I	613.10	1	200	CY	TOTAL
				120						120		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	3	ITEM 641.15 - PORTABLE CHANGEABLE MESSAGE SIGN		
				100						100		LF	CHAIN-LINK FENCE, 6 FEET	620.12	EST.	2	EA	US ROUTE 5
				16						16		EACH	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 6 FEET	620.21	EST.	2	EA	I-91 AT ROLLING ROAD BLOCK
							404			404		LF	SNOW BARRIER, GALVANIZED	620.75	-	2	EA	AT EXIT 4
				275						275		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-	2	EA	AT EXIT 5
				2						2		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-	8	EA	SUBTOTAL
							4			4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED NETC 2 RAIL	621.72	-	0	EA	ROUNDING
				126						126		LF	REMOVE AND RESET GUARDRAIL	621.75	-	8	EA	TOTAL
				77						77		LF	ADJUST HEIGHT OF GUARDRAIL	621.79	-	ITEM 649.31 - GEOTEXTILE UNDER STONE FILL		
				505						505		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-	19	SY	ROADWAY
				190					1260	1450		LF	TEMPORARY TRAFFIC BARRIER	621.90	40	262	SY	STONE SLOPE, ABUTMENT 1
								1		1		LS	FIELD OFFICE, ENGINEERS	631.10	-	308	SY	STONE SLOPE, ABUTMENT 2
								1		1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-	589	SY	SUBTOTAL
								1		1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-	11	SY	ROUNDING
								1		1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-	600	SY	TOTAL
					520					520		HR	EMPLOYEE TRAINEESHIP	634.10	EST.			
				1						1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
				1						1		LS	TRAFFIC CONTROL (I-91 ROLLING ROAD BLOCK)	641.10	-			
				1						1		LS	TRAFFIC CONTROL (I-91 TEMPORARY LANE CLOSURE)	641.10	-			
									1	1		LS	TRAFFIC CONTROL (TEMPORARY DETOUR)	641.10	-			
				6					2	8		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
				1700						1700		LF	DURABLE 4 INCH WHITE LINE	646.400	-			
				2900						2900		LF	DURABLE 4 INCH YELLOW LINE	646.410	-			
				100						100		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST.			
						600				600		SY	GEOTEXTILE UNDER STONE FILL	649.31	11			
						110				110		SY	GEOTEXTILE FOR SILT FENCE	649.51	2			
						230				230		LB	SEED	651.15	3			
						130				130		LB	SEED, WINTER RYE	651.17	5			
						1580				1580		LB	FERTILIZER	651.18	10			
						6.5				6.5		TON	AGRICULTURAL LIMESTONE	651.20	0.2			
						6.5				6.5		TON	HAYMULCH	651.25	0.2			
						810				810		CY	TOPSOIL	651.35	9			
						7220				7220		SY	TEMPORARY EROSION MATTING	653.20	12			

PROJECT NAME: PUTNEY
PROJECT NUMBER: IM 091-1(31)



FILE NAME: ...\\05-07 z93d48quantity.pxf PLOT DATE: 7/8/2009
PROJECT LEADER: G. BOGUE DRAWN BY: E. ALLING
DESIGNED BY: E. ALLING CHECKED BY: G. GOYETTE
QUANTITY SHEET 2 SHEET 6 OF 75