STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																								
STATION 16+81, RT ROUTE 15	R4-7, KEEP RIGHT	1	24	30	5						1					X		1															INSTALL NEW SIGN ON NEW POST		SHS PAGE 1-67
	OM1-1, OBJECT MARKER	1	18	18	2.25	ISLAND WEST END																											INSTALL NEW SIGN ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		SHS PAGE 11-1
STATION 17+20, RT ROUTE 15	R6-1, ONE WAY						2				1					X		1															INSTALL NEW SIGN ON NEW POST		
STATION 17+75, LT ROUTE 15	M3-4, WEST	1	24	12	2						1					X		1															INSTALL NEW SIGNS (BACK TO BACK) ON NEW POST		STD. E-136B
	M1-6A, STATE ROUTE 15	1	24	24	4																												INSTALL NEW SIGN ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		STD. E-136B
STATION 18+18, RT ROUTE 15	D1-1, GUIDE SIGN						1				2					X		2															RELOCATE EXISTING SIGN ON NEW POSTS		
	M3-2, EAST						1																										RELOCATE EXISTING SIGN ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
	M1-6A, STATE ROUTE 15						1																										RELOCATE EXISTING SIGN ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 18+37, LT ROUTE 15	R4-7, KEEP RIGHT	1	24	30	5	ISLAND WEST END					1					X		1															INSTALL NEW SIGN ON NEW POST		SHS PAGE 1-67
	OM1-1, OBJECT MARKER	1	18	18	2.25																												INSTALL NEW SIGN ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		SHS PAGE 11-1
STATION 18+91, RT ROUTE 15	D1-1, GUIDE SIGN ROLAND CT.						1				1					X		1															RELOCATE EXISTING SIGN ON NEW POST		
	D1-1, GUIDE SIGN E. ALLEN ST.						1																										RELOCATE EXISTING SIGN ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 18+94, RT ROUTE 15	R4-7, KEEP RIGHT	1	24	30	5	CONCRETE ISLAND WEST END					1						X	1	1														INSTALL NEW SIGN ON NEW POST		SHS PAGE 1-67
	R3-4, NO U TURN	1	24	24	4																												INSTALL NEW SIGNS BACK TO BACK ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		SHS PAGE 1-26
	OM1-1, OBJECT MARKER	1	18	18	2.25																												INSTALL NEW SIGNS BACK TO BACK ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		SHS PAGE 11-1
	R3-4, NO U TURN	1	24	24	4																												INSTALL NEW SIGNS BACK TO BACK ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		SHS PAGE 1-26
												FT	FT	FT	FT	FT 96.5	FT 16		EA 1	LB	LB	LB		LB	LB	LB	LB								
				TOTALS	SF 35.75	SF	EA. 7	SF				FT			FT 112.5					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND THE "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WINOOSKI
PROJECT NUMBER: NH 089-3(65)

FILE NAME: z94a198tss.dgn
PROJECT LEADER: KEN UPMAL
DESIGNED BY: J.SOBEL
TRAFFIC SIGN SUMMARY SHEET 3

PLOT DATE: 2/22/2010
DRAWN BY: J.WILTSHIRE
CHECKED BY: D.FLYNN
SHEET 46 OF 67