STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAMEMED REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
	OMI-1, OBJECT MARKER	1	18	18	2.25																												INSTALL NEW SIGNS BACK TO BACK ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		SHS PAGE 11-1
STATION 19+32, RT ROUTE 15	R4-7, KEEP RIGHT	1	24	30	5						1					X		1	1														INSTALL NEW SIGN ON NEW POST		SHS PAGE 1-67
	OMI-1, OBJECT MARKER	1	18	18	2.25																												INSTALL NEW SIGN ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		SHS PAGE 11-1
STATION 19+85, LT ROUTE 15	R2-1, SPEED LIMIT	1	24	30	5						1						X	1					LID INSTALLED NEW SIGNS ON OLD POST, AS DETAILED IM 40 ON SHEET 43										INSTALL NEW SIGN ON NEW POST		SHS PAGE 1-10
	R8-3A, NO PARKING	1	24	24	4																												INSTALL NEW SIGN ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		SHS PAGE 1-104
STATION 20+38, LT ROUTE 15	R1-1, STOP	1	30	30	6.25						1					X		1	1														INSTALL NEW SIGN ON NEW POST		SHS PAGE 1-1
STATION 20+93, LT ROUTE 15	R10-7, DO NOT BLOCK INTERSECTION	1	24	30	5						1					X		1	1														INSTALL NEW SIGN ON NEW POST		SHS PAGE 1-136
												FT	FT	FT	FT	FT 41	FT 15		EA 2	LB	LB	LB		LB	LB	LB	LB								

	SF	SF	EA.	SF		FT	FT	LB	EA.	LB	EA.	EA.	LB
TOTALS	29.75						56						

	SF	SF	EA.	SF		FT	FT	LB	EA.	LB	EA.	EA.	LB
SHEET 44 TOTALS	31.57	297	8				148.75						
SHEET 45 TOTALS	46.75		8				115.5						
SHEET 46 TOTALS	35.75		7				112.5						
SHEET 47 TOTALS	29.75						56.00						
GRAND TOTALS	143.82	297	23				432.75						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND THE "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WINOOSKI
PROJECT NUMBER: NH 089-3(65)

FILE NAME: z94a198tss.dgn
PROJECT LEADER: KEN UPMAL
DESIGNED BY: J.SOBEL
TRAFFIC SIGN SUMMARY SHEET 4

PLOT DATE: 2/23/2010
DRAWN BY: J.WILTSHIRE
CHECKED BY: D.FLYNN
SHEET 47 OF 67