

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY (#1_NB)	TRAINING	EROSION CONTROL	BRIDGE (BR3_NB)	BRIDGE (BR3_SB)	FULL C.E. ITEMS	ROADWAY (#1_SB)	BROAD BROOK ROAD	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS		
			0.55	0.45				1		LS	STRUCTURAL PAINTING, SHOP APPLIED (11 TONS)	513.25						
			0.55	0.45				1		LS	CONTAINMENT & ENVIRONMENTAL PROTECTION, SHOP (11 TONS)	513.35						
			0.55	0.45				1		LS	SURFACE PREPARATION, SHOP (11 TONS)	513.40						
			108	90				198		GAL	WATER REPELLENT, SILANE	514.10						
			44	32				76		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10						
			44	32				76		LF	BRIDGE EXPANSION JOINT, FINGER PLATE	516.12						
			1270	920				2190		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20						
			552	552				1104		LF	REMOVAL OF EXISTING RAILING	525.10						
			0.5	0.5				1		LS	MAINTENANCE OF STRUCTURES AND APPROACHES	527.10						
			1000	1000				2000		SY	REMOVAL OF BRIDGE PAVEMENT	529.10						
			1	1				2		EACH	PARTIAL REMOVAL OF STRUCTURE (DECK AND SUBSTRUCTURES)	529.20						
			1	1				2		EACH	PARTIAL REMOVAL OF STRUCTURE (STRUCTURAL STEEL)	529.20						
			12	10				22		EACH	BEARING DEVICE ASSEMBLY, PREFORMED FABRIC PAD	531.10						
			12	10				22		EACH	BEARING DEVICE ASSEMBLY, ELASTOMERIC PAD	531.11						
			6	2				8		SY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS I	580.13						
			31	11				42		SY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS II	580.14						
			2	2				4		CY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS III	580.15						
			608				280	888		LF	18" CPEP	601.0915						
			2				1	3		EACH	18" CPEP ELBOW	601.5814						
			3				1	4		EACH	18" CPEPES	601.7015						
			4				1	5		EACH	PRECAST REINFORCED CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.20						
			2100		1330	960		4390		CY	STONE FILL, TYPE II	613.11						
					4040			4040		CY	STONE FILL, TYPE IV	613.13						
			1725				155	1880		LF	TREATED TIMBER CURB	616.35						
					200	50		250		LF	WOVEN WIRE FENCE WITH STEEL POSTS	620.25						
					200	50		250		LF	REMOVAL OF EXISTING FENCE	620.55						
			1940				1440	3580	200	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21						
			2				2	4		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50						
							1	1		EACH	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.53						
			2				1	3		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60						
			1680				1460	3140		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80						
			4590				2040	6630		LF	TEMPORARY TRAFFIC BARRIER	621.90						
			1430					1430		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95						
			1240				1240	2480		HR	UNIFORMED TRAFFIC OFFICERS	630.10						
					600	600		1200		HR	FLAGGERS	630.15						
								1		LS	FIELD OFFICE, ENGINEERS	631.10						
								1		LS	TESTING EQUIPMENT, CONCRETE	631.16						
								1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17						
								1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25						
								1040		HR	EMPLOYEE TRAINEESHIP	634.10						
			0.5				0.5	1		LS	MOBILIZATION/DEMOBILIZATION	635.11						

PROJECT NAME: **GUILFORD** SUMMARY
PROJECT NUMBER: **IM 091-1(33)**
FILE NAME: 95a176quantity.dgn PLOT DATE: 06/11/2008
PROJECT LEADER: Farnsworth DRAWN BY: Weeber
DESIGNED BY: STR1 CHECKED: Farnsworth
QUANTITY SHEET #2 SHEET **3A** OF 114

REVISION	DATE	BY	DESCRIPTION
△	07/16/2008	VAOT	ADDED PAY ITEM.