

QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
	ROADWAY (B1_NB)	TRAINING	EROSION CONTROL	BRIDGE (BR3_NB)	BRIDGE (BR3_SB)	FULL C.E. ITEMS	ROADWAY (B1_SB)	BROAD BROOK ROAD		GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
	0.5						0.5			1		LS	TRAFFIC CONTROL	641.10				
	2						1			3		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
	1						1			2		EACH	PORTABLE ARROW BOARD	641.16				
	10									10		DAY	PORTABLE CHANGEABLE MESSAGE SIGN RENTAL	641.17				
	3000						820			3820		LF	6 INCH WHITE LINE	646.214				
	2640						1460			4100		LF	6 INCH YELLOW LINE	646.215				
	300									300		LF	12 INCH WHITE LINE	646.24				
	1170						1000			2170		LF	TEMPORARY 6 INCH WHITE LINE, TYPE II TAPE	646.621				
	8690						5370			14060		LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622				
	1360						1370			2730		LF	TEMPORARY 6 INCH YELLOW LINE, TYPE II TAPE	646.631				
	12460						8270			20730		LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632				
	1430						810			2240		EACH	RAISED PAVEMENT MARKERS, TYPE II	646.75				
	1120									1120		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85				
	4800						3900			8700		SF	PAVEMENT MARKING MASK	646.86				
	4170				4160	1440				9770		SY	GEOTEXTILE UNDER STONE FILL	649.31				
			1270							1270		SY	GEOTEXTILE FOR SILT FENCE	649.51				
			510							510		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
			100							100		LB	SEED	651.15				
			100							100		LB	SEED, WINTER RYE	651.17				
			840							840		LB	FERTILIZER	651.18				
			4							4		TON	AGRICULTURAL LIMESTONE	651.20				
			4							4		TON	HAY MULCH	651.25				
	2380				1980		50			4410		SY	GRUBBING MATERIAL	651.40				
			1							1		LS	EPSC PLAN	652.10				
			50							50		HR	MONITORING EPSC PLAN	652.20				
			1							1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
			4610							4610		SY	TEMPORARY EROSION MATTING	653.20				
			1790							1790		SY	PERMANENT EROSION MATTING	653.21				
			20							20		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
			40							40		CY	VEHICLE TRACKING PAD	653.35				
			13							13		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
			4300							4300		LF	PROJECT DEMARCATION FENCE	653.55				
	20						20			40		SF	TRAFFIC SIGNS, TYPE A	675.20				
	60						60			120		LF	FLANGED CHANNEL SIGN POST	675.301				
	9						7			16		EACH	REMOVING SIGNS	675.50				
	9						7			16		EACH	ERECTING SALVAGED SIGNS	675.60				
	20									20		EACH	DELINEATOR WITH FLEXIBLE POST	676.20				
					100	100				200		CY	SPECIAL PROVISION (BRIDGE RAILING, F-SHAPE CONCRETE)	900.608				
	4						4			8		EACH	SPECIAL PROVISION (GUARDRAIL APPROACH SECTION TO F-SHAPE CONCRETE RAIL)	900.620				
					0.5	0.5				1		LS	SPECIAL PROVISION (PUBLIC PROTECTION FOR BRIDGE PROJECTS)	900.645				