



- ONE - GIRDER - G2C**
1. FOR GIRDER STANDARD DETAILS SEE DRAWING X41.
  2. FOR CAMBER AND FLANGE DIAGRAMS SEE DRAWING C403.
  3. FOR HORIZONTAL CURVING DIAGRAM SEE DRAWING HC401.
  4. FOR GENERAL NOTES SEE DRAWING GN301.

ABM INFO		BILL OF MATERIAL				JOB NO.		DRAWING NO.		REV.
PAGE	LINE	MARK	QTY	MARK	MATERIAL	LENGTH		REMARKS	WT	PROCUREMENT NOTES
						FT	INCHES			
		G2C	1		GIRDER					7046
401	Q		1	wa	PL 1/2 x 33 7/8	37	1 3/8	(H270-50WT2) (H2-3)		
401	J		1	ta	PL 5/8 x 16	37	1 3/8	(H270-50WT2) (H2-3)		
401	E		1	ba	PL 5/8 x 16	37	1	(H270-50WT2) (H2-3)		
402	B		4	x41a	PL 1/2 x 29 3/4	1	7	(H270-50WT2) (H2-3)		
402	C		4	x41b	PL 5/8 x 16	2	7	(H270-50WT2) (H2-3)		
402	D		8	x41c	PL 5/8 x 7	2	7	(H270-50WT2) (H2-3)		
402	F		2	x41d	PL 1/2 x 16	1	3 3/8	FILL		
402	G		2	x41f	PL 1/2 x 16	1	3 3/8	FILL		
402	M		2	x41t	PL 1/2 x 5	2	8 3/4			
402	M		1	x41ab	PL 2 x 5	2	8 3/4			
402	M		1	x41v	PL 2 x 5	2	8 3/4			

**TVGA**  
Engineering, Surveying, P.C.

NO EXCEPTIONS TAKEN  REJECTED  
 FURNISH AS CORRECTED  
 REVISE AND RESUBMIT

ENGINEER has reviewed Shop Drawings and Samples and other data which Contractor is required to submit only for conformance with the information given in the Contract Documents and compliance with the design concept of the completed Project as a furnishing whole as indicated in the Contract Documents. Such review does not extend to means, methods, techniques, sequences or procedures of construction or to safety precautions and programs incident thereto. Contractor is responsible for dimensions to be confirmed and coordinated at the job site for information that contains solely to the fabrication processes or to techniques of construction; and for coordination of the work of all trades.

BY: *[Signature]*  
DATE: 08-11-2008

OUT FOR APPROVAL	<i>[Signature]</i>									
OUT FOR APPROVAL										
ISSUED TO SHOP										
FIELD & OFFICE										

REV.	REMARKS	DATE	DWN	CHK	APP	Q.A.	NO.	DIA.	LGT	TYPE	WASHER
	MATERIAL: M270 GR. 50W (UN)										
	ELECTRODES:										
	HOLES:										
	SHOP BOLTS:										
	SURFACE PREP. & PAINT: - STEEL WITHIN 10'-0" OF ABUT. 2 SHALL BE PAINTED (SEE GN301) - ALL OTHER STEEL SHALL BE BLAST CLEANED AND LEFT UNPAINTED.										
	DESCRIPTION: GIRDER - G2C										
	JOB: I-89 NB OVER LITTLE RIVER										
	I-89 IMPROVEMENTS										
	BETWEEN TOWNS OF MIDDLESEX & BOLTON										
	COUNTY OF WASHINGTON VERMONT										
	PROJ NO. IM-089-2(26)										
	CUSTOMER: VERMONT AGENCY OF TRANSPORTATION										
	<b>CASCO BAY STEEL STRUCTURES, INC.</b>										
	75 SPRING HILL ROAD SACO, MAINE 04072										
	PHONE (207) 282-7360 FAX. (207) 282-1179										
	JOB NO. 119-48N										
	DRG. NO. 412										
	REV. <input type="checkbox"/>										

THE BAY AREA CONSULTING ENGINEERS, INC. 2008-08-11-2008