



ARROW DETAIL

COLORS
LEGEND & BORDER - WHITE (REFL.)
BACKGROUND - BLUE

GENERAL:
ALL DIMENSIONS IN INCHES.

COLORS:
THE SIGNS SHOWN ON THIS SHEET SHALL BE AS DETAILED FOR EACH SIGN. THE COLORS SHALL CONFORM WITH THE COLORS ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS AND APPROVED BY THE DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION.

MATERIALS:
THE SIGN BASE MATERIALS USED FOR SIGNS SHOWN ON THIS SHEET MAY BE ANY OF THE FOLLOWING MINIMUM THICKNESSES NOTED.

FLAT SHEET ALUMINUM	24" X 24"
HIGH DENSITY OVERLAID PLYWOOD	24" X 30"
GALVANIZED FLAT SHEET STEEL	0.080"
	1/2"
	16 GAGE

ENCAPSULATED LENS REFLECTIVE SHEETING SHALL BE USED FOR THE SIGN BACKGROUND WHERE NOTED.

THE REFLECTIVE MATERIAL SHALL BE AASHTO TYPE II OR III WHITE REFLECTIVE SHEETING APPLIED TO THE ENTIRE BACKGROUND OF THE SIGN. THE TEXT OF THE SIGNS MAY BE LETTERING FILM, SILK SCREENED OR HANDPAINTED. HAND PAINTING MUST BE COMPARABLE IN QUALITY TO THE RESULTS OBTAINED BY SILK SCREENING.

TEXT DESIGN:
LETTERS, DIGITS, ARROWS, SPACINGS, AND TEXT DIMENSIONS SHALL CONFORM WITH THE STANDARD ALPHABETS AND DESIGNS PRESCRIBED IN THE 'MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES'.

SPECIFICATIONS:
THE SIGNS SHALL MEET THE VERMONT STANDARD SPECIFICATIONS FOR 'TRAFFIC SIGNS'.

SIGN DETAILS	
FOR LYNDON REST AREA	
PREPARED BY <u>LCS</u>	DATE <u>9/95</u>
CHECKED BY _____	DATE _____
DESIGN SUPERVISOR <u>DLP</u>	DATE _____
PROJ. <u>LYNDON</u>	
<u>IM-BLDG(2)</u>	
SHEET <u>21</u> OF <u>29</u> SHEETS	

lyndon3.i
/traf/enrg1/lyndon.dgn