QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EROSION CONTROL	EMPLOYEE TRAINEESHIP	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		500	500	CY	COMMON EXCAVATION	203.15	EST.
		365	365	CY	TRENCH EXCAVATION OF ROCK	204.21	EST.
		9800	9800	TON	AGGREGATE SHOULDERS	402.12	85
		1900	1900	LF	6'' UNDERDRAIN	605.10	EST.
		300	300	LF	8'' UNDERDRAIN	605.11	EST.
		300	300	LF	12'' UNDERDRAIN	605.13	EST.
		1	1	HR	BULLDOZER RENTAL, TYPE I (N.A.B.I.)	608.10	EST.
		300	300	HR	ALL PURP. EXCAVATOR RENTAL, TYPE I	608.25	EST.
		300	300	HR	POWER BROOM RENTAL	608.30	EST.
		100	100	HR	TRUCK RENTAL	608.37	EST.
		1	1	HR	LOADER RENTAL, TYPE I (N.A.B.I.)	608.40	EST.
		30	30	CY	STONE FILL, TYPE I	613.10	EST.
		1000	1000	LF	TREATED TIMBER CURB	616.35	EST.
		5	5	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	EST.
		17225	17225	LF	STEEL BEAM GUARD RAIL	621.20	200
		274	274	EA	MODIFIED ECCENTRIC LOADER TERMINAL	621.52	-
		2	2	EA	ANCHOR FOR STEEL BEAM GUARD RAIL	621.60	-
		9	9	EA	GUARD RAIL APPROACH SECTION, TYPE I	621.70	-
		20	20	EA	REPLACE GUARD RAIL POST ASSEMBLY	621.76	EST.
		23700	23700	LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	106
		1000	1000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
		1800	1800	HR	FLAGGERS	630.15	EST.
	540		540	HR	EMPLOYEE TRAINEESHIP	634.10	
		1	1	LS	MOBILIZATION	635.10	EST.
		1	1	LS	TRAFFIC CONTROL	641.10	EST.
		2	2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	EST.
		2	2	EA	PORTABLE ARROW BOARD	641.16	EST.
360			360	LB	SEED	651.15	EST.
3000			3000	LB	FERTILIZER	651.18	EST.
12			12	TON	AGRICULTURAL LIMESTONE	651.20	EST.
12			12	TON	HAY MULCH	651.25	EST.
1500			1500	CY	TOPSOIL	651.35	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DRAWN BY SQDA DATE 2-5-96
SQUAD LEADER BT NYQUIST
DESIGN FILE NO. /SQDA/96A376/DA376.DGN
SPARM FILE DA376QU DATE PLOTTED 16-SEP-1996
PROJ. NAME STATEWIDE GUARD RAIL
PROJ. NO. IMG GDRL(1)
SHEET 2 OF 28 SHEETS

: Sheet Number: 2