EARTHWORK AND DRAINAGE SUMMARY SHEET - STATEWIDE GUARD RAIL IMG GDRL(1)

MILE MARKER	MILE MARKER	POSITION	AGGREGATE SHOULDER MATERIAL (TONS) 402.12						REMOVAL & DISPOSAL OF GUARDRAIL 621.80	STEEL BEAM GUARDRAIL W/STL POST 621.20		M.E.L.T. (EACH) 621.52	DELINEATORS (EACH)	UNDER DRAIN	APPROACH SECTION TYPE I 621.70	ANCHOR 621.60		REMARKS
I-91 NORTH BOUND SECTION 1																		
5.93	5.97	LT	35						112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
8.51	8.55	LT	35						112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
10.25	10.29	LT	35						112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
10.41	10.45	LT	35						112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
I-91 SOUTH BOUND SECTION 1																		
10.72	10.69	RT	35						112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
10.41	10.38	RT	35						112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
8.69	8.66	RT	35						112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
6.07	6.04	RT	35						112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
0.24		RT	35						37.5	12.5		1	1					"EXIT 1, RAMP D: EXISTING TEXAS TWIST SEE SHEET 19 FOR CONSTRUCTION TREATMENT"
SHEET	TOTAL		315						937.5	612.5		9	9	0	0	0	0	

DRAWN BY SQUAD A/JFG DATE FEB '96
SQUAD LEADER NYQUIST
DESIGN FILE NO. /SQDA/95A376/DA376.DGN
DARM FILE DA376SQ1J DATE PLOTTED 16-SEP-1996
PROJ. NAME STATEWIDE GUARD RAIL
PROJ. NO. IMG GDRL(1)
SHEET 3 OF 28 SHEETS

: Sheet Number: 3