EARTHWORK AND DRAINAGE SUMMARY SHEET - STATEWIDE GUARD RAIL IMG GDRL(1)

MILE MARKER	MILE MARKER	POSITION	AGGREGATE SHOULDER MATERIAL (TONS) 402.12						REMOVAL & DISPOSAL OF GUARDRAIL 621.80	STEEL BEAM GUARDRAIL W/STL POST 621.20		M.E.L.T. (EACH) 621.52	DELINEATORS (EACH)	UNDER DRAIN	APPROACH SECTION TYPE I 621.70	ANCHOR 621.60		REMARKS
I-91 SOUTHBOUND		SECTION 4 CONTINUED																
143.82		RT	35						37.5	12.5		1	1	40				EXISTING TEXAS TWIST SEE SHEET 19 FOR CONSTRUCTION TREATMENT
143.13		LT	35						37.5	12.5		1	1	20				EXISTING TEXAS TWIST SEE SHEET 19 FOR CONSTRUCTION TREATMENT
142.17		LT	35						37.5	12.5		1	1	20				EXISTING TEXAS TWIST SEE SHEET 19 FOR CONSTRUCTION TREATMENT
141.53	141.49	LT	35						112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
141.53	141.49	RT	35						112.5	75.0		1	1	40				EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
141.35		RT	35						37.5	12.5		1	1					EXISTING TEXAS TWIST SEE SHEET 19 FOR CONSTRUCTION TREATMENT
140.70		RT	35						37.5	12.5		1	1	40				EXISTING TEXAS TWIST SEE SHEET 19 FOR CONSTRUCTION TREATMENT
140.69		LT	35						37.5	12.5		1	1	40				EXISTING TEXAS TWIST SEE SHEET 19 FOR CONSTRUCTION TREATMENT
140.01	139.97	RT	35						112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
140.01	139.97	LT	35						112.5	75.0		1	1	40				EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
138.88		LT	35						37.5	12.5		1	1					EXISTING TEXAS TWIST SEE SHEET 19 FOR CONSTRUCTION TREATMENT
138.88		RT	35						37.5	12.5		1	1					EXISTING TEXAS TWIST SEE SHEET 19 FOR CONSTRUCTION TREATMENT
137.83		LT	35						37.5	12.5		1	1					EXISTING TEXAS TWIST SEE SHEET 19 FOR CONSTRUCTION TREATMENT
137.32		LT	35						37.5	12.5		1	1	40				EXISTING TEXAS TWIST SEE SHEET 19 FOR CONSTRUCTION TREATMENT
137.20	137.17	RT	35						112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
137.17	RAMP B	LT	35						112.5	75.0		1	1					EXIT 23 TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
134.25	134.08	LT	35						112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
131.48	131.45	RT	35						130.0	150.0		1	1					INSTALL NEW RAIL ADJACENT TO SHOULDER OF ROAD (REMOVE SB RAIL ONLY)
132.66	132.62	LT	35						112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
131.10		LT	35						37.5	12.5		1	1	40				EXISTING TEXAS TWIST SEE SHEET 19 FOR CONSTRUCTION TREATMENT
130.60		LT	35						37.5	12.5		1	1	40				EXISTING TEXAS TWIST SEE SHEET 19 FOR CONSTRUCTION TREATMENT
129.84	129.76	LT	35						112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
129.83	129.76	RT	35						112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
RAMP C	EXIT 20	RT	35						200.0	125.0		1	1		1			EXISTING BOX BEAM GUARDRAIL SEE SHEET 16 FOR CONSTRUCTION TREATMENT
128.97	128.91	RT	35						275.0	187.5		1	1		1			EXISTING BOX BEAM GUARDRAIL SEE SHEET 16 FOR CONSTRUCTION TREATMENT
SHEET	TOTAL		875						2180.0	1362.5		25	25	360	2	0		

DRAWN BY SQUAD A/JFG DATE FEB '96
SQUAD LEADER NYQUIST
DESIGN FILE NO. /SQDA/95A376/DA376.DGN
IPARM FILE DA376S07.I DATE PLOTTED 16-SEP-1996
PROJ. NAME STATEWIDE GUARD RAIL
PROJ. NO. IMG GDRL(1)
SHEET 9 OF 28 SHEETS

Sheet Number: 9