EARTHWORK AND DRAINAGE SUMMARY SHEET - STATEWIDE GUARD RAIL IMG GDRL(1)

MILE MARKER	MILE MARKER	POSITION	AGGREGATE SHOULDER MATERIAL (TON) 402.12						REMOVAL & DISPOSAL OF GUARDRAIL 621.80	STEEL BEAM GUARDRAIL W/STL POST 621.20		M.E.L.T. (EACH) 621.52	DELINEATORS (EACH)	UNDER DRAIN	APPROACH SECTION TYPE I 621.70	ANCHOR 621.60		REMARKS
I 89 NB	SECT 7																	
RAMP G	EX 14E								37.5	12.5		1	1					"EXISTING TWO RAIL ALUMINUM; EXIT 14E, US-2 SEE SHEET 18 FOR CONSTRUCTION TREATMENT"
I 89 SB	SECT 7																	
RAMP B	EX 14W								37.5	12.5		1	1					"EXISTING TWO RAIL ALUMINUM; EXIT 14W, US-2 SEE SHEET 18 FOR CONSTRUCTION TREATMENT"
I 89 NB	SECT 8																	
107.30	107.34	RT							112.5	75.0		1	1					EXISTING TWO RAIL ALUMINUM SEE SHEET 18 FOR CONSTRUCTION TREATMENT
RAMP A	EX 19	RT							37.5	12.5		1	1					EXISTING TWO RAIL ALUMINUM EXIT 19 SEE SHEET 18 FOR CONSTRUCTION TREATMENT
SHEET	TOTAL		0	0					225.0	112.5		4	4	0	0	0		

DRAWN BY SQUAD A/JFC DATE FEB '96
SQUAD LEADER MYOUST
DESIGN FILE NO. /SQDA/95A376/DA376.DGN
IPARM FILE DA376SU DATE PLOTTED 16-SEP-1996
PROJ. NAME STATEWIDE GUARD RAIL
PROJ. NO. IMG GDRL(1)
SHEET 13 OF 28 SHEETS

Sheet Number: 13