STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAMED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
	NORTHBOUND																																		
III.14LT.		1	36	36	9						1			X																			R3-4		E-143
III.30LT.		1	12	36	3						1			X																			OM-1		E-107
III.30RT.		1	12	36	3						1			X																			OM-1		E-107
III.50LT.		1	36	36	9						1			X																			R3-4		E-143
112.00RT.	MILE 112	1	12	48	4						1			X																			D10-3		E-139
112.08RT.	ENTERING TOWN OF FAIRFIELD	1	36	24	6						1			X																					E-131
112.29RT.	ENTERING TOWN OF ST.ALBANS	1	36	24	6						1			X																					E-131
112.48RT.	EXIT 19	1	96	24.5	16.33																														E-131
	7 36 104 St. Albans 1 MILE	1	180	120		150					2																		2	771	W8X21		SET BOLT TENSION TO 25 KIPS	33	
112.67RT.	TO 105 Enosburg Richford NEXT RIGHT	1	174	96		116					2																	2		524	W6X15		SET BOLT TENSION TO 24 KIPS	33	
113.00RT.	MILE 113	1	12	48	4						1			X																			D10-3		E-139
113.07RT.	EXIT 19	1	96	24.5	16.33																														
	7 36 104 St. Albans ½ MILE	1	180	120		150					2																		2	780	W8X21		SET BOLT TENSION TO 25 KIPS	33	
113.21RT.	ST ROUTE ST ROUTE STATE POLICE H	1	138	96		92					2																	2		500	W6X15		VD-367 SET BOLT TENSION TO 19 KIPS	34	
113.33LT.		1	36	36	9						1			X																			R3-4		E-143
												FT	FT	FT 118	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
												FT			FT					LB			EA.	LB				EA.	EA.	LB					
	TOTALS		SF 86	SF 508	EA.	SF						118																4	4	2575					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: FAIRFAX-FAIRFIELD-ST. ALBANS	PROJECT NO.: IM 089-3(27)
DESIGN FILE NAME: 87A007B/DESIGN/DA007FRM.DGN	
IPARM FILE NAME: DA007SSI.I	PLOT DATE: 19-AUG-2000
SURVEYED BY:	SURVEY DATE:
SQUAD LEADER: ANN KREIS	DRAWN BY: JHK
	SHEET: 35 OF 370