

QUANTITY SHEET

**STATE OF VERMONT
AGENCY OF TRANSPORTATION**

SOUTHBOUND										NORTHBOUND										SUMMARY OF ESTIMATED QUANTITIES					
FULL E&C	TRAINING	EROSION CONTROL	BR 86-5 OUTLET 100 SERIES	BR 87S 200 SERIES	BR 87-3S 300 SERIES	BR 88S 400 SERIES		BR 88-3 OUTLET 500 SERIES	ROADWAY	FULL E&C	TRAINING	EROSION CONTROL	BR 86-5 INLET 100 SERIES	BR 87N 200 SERIES	BR 87-3N 300 SERIES	BR 88N 400 SERIES		BR 88-3 INLET 500 SERIES	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING	
									25										25	50	HR	POWER BROOM RENTAL	608.30		
									25										25	50	HR	TRUCK RENTAL	608.37		
									25										25	50	HR	LOADER RENTAL TYPE I	608.40		
									25										25	50	HR	LOADER RENTAL TYPE II	608.41		
									850										850	1700	MGAL	DUST CONTROL W/WATER	609.10	EST.	
									10										10	20	TON	DUST AND ICE CONTROL W/CALC. CHLORIDE	609.15	EST.	
		155							60			155							15	385	CY	STONE FILL, TYPE I	613.10	6	
			85						2830				75			260			55	2885	CY	STONE FILL, TYPE II	613.11	3	
						260										655				680	CY	STONE FILL, TYPE III	613.12		
						655														1310	CY	STONE FILL, TYPE IV	613.13		
													1							1	LS	TEMPORARY RELOCATION OF STREAM (CHANNEL STA. 13+90.5)	614.10		
																				1	LS	TEMPORARY RELOCATION OF STREAM (CHANNEL STA. 31+04.1)	614.10		
																			150	150	LF	VERTICAL GRANITE CURB	616.21		
				160											160		160			640	LF	CAST-IN PLACE CEMENT CONCRETE CURB, TYPE B (MOD. SILICA-FUME CONCRETE)	616.28		
									2340										1420	3760	LF	TREATED TIMBER CURB	616.35	23	
									115										110	225	EA	YIELDING MARKER POSTS	619.17	10	
									7470											7470	LF	CHAIN-LINK FENCE, 6 FEET	620.12	18	
									1420										2880	4300	LF	WOVEN WIRE FENCE W/ STEEL POSTS	620.25	50	
																			2	2	EA	STEEL BRACE FOR WOVEN WIRE FENCE(10 EST)	620.40		
									8890										2860	11750	LF	REMOVAL OF EXISTING FENCE (MODIFIED)	620.55	48	
				120											120		160			560	LF	SNOW BARRIER - GALVANIZED	620.75		
									10687										10547	21234	LF	STEEL BEAM GUARD RAIL	621.20		
									22										11	33	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505		
									6										11	17	EA	ANCHOR FOR STEEL BEAM RAIL	621.60		
				4											4		4			16	EA	GUARD RAIL APPROACH SECTION, NETC 2 RAIL	621.72		
									14500										12500	27000	LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	91	
									18600										15600	34200	LF	TEMPORARY TRAFFIC BARRIER	621.90	230	
									1750										1750	3500	LF	TEMPORARY TRAFFIC BARRIER - MODIFIED	621.90	60	
																				82	LF	PVC SEWER PIPE (MOD. 4'' PERFORATED)	628.35		
									3400										5500	8900	HR	UNIFORMED TRAFFIC OFFICERS	630.10		
0.5									9000										8500	17500	HR	FLAGGERS	630.15		
0.5										0.5										1	LS	FIELD OFFICE-ENGINEERS	631.10		
0.5										0.5										1	LS	FIELD OFFICE-SOILS & MATERIALS	631.11		
0.5										0.5										1	LS	TESTING EQUIPMENT - CONCRETE	631.16		
0.5										0.5										1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17		
0.5										0.5										1	LU	FIELD OFFICE - TELEPHONE(NOT A BID ITEM)	631.25		
	1300										1300									2600	HR	EMPLOYEE TRAINEESHIP	634.10		
									0.5										0.5	1	LS	MOBILIZATION	635.10	EST.	
									0.5										0.5	1	LS	TRAFFIC CONTROL	641.10	EST.	
									1										1	2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15		
									2										2	4	EA	PORTABLE ARROW BOARDS	641.16		
									43800											43800	LF	6'' WHITE LINE	646.214	117	
									34400											34400	LF	6'' YELLOW LINE	646.215	109	
																			1500	1500	LF	DURABLE 4'' WHITE LINE	646.40		
																			1160	1160	LF	DURABLE 4'' YELLOW LINE	646.41		
									23500										24600	48100	LF	DURABLE 6'' WHITE LINE	646.414	189	
									19300										20800	40100	LF	DURABLE 6'' YELLOW LINE	646.415	219	
																			320	320	LF	DURABLE 8'' YELLOW LINE	646.42		
									380										425	805	LF	DURABLE ''12'' WHITE LINE	646.44		
																			36	36	LF	DURABLE 24'' STOP BAR	646.46		
																			33	33	EA	DURABLE LETTER OR SYMBOL	646.50		

[illegible]

SURVEYED BY _____ DATE _____
DRAWN BY _____ SQUAD B _____ DATE _____
SQUAD LEADER DELLA SANTA _____
DESIGN FILE NO. 87A007B/DESIGN/DA007FRM.DGN
IPARM FILE DA007Q53 DATE PLOTTED 17-NOV-2000
PROJ. NAME FAIRFAX-FAIRFAX-ST. ALBANS
PROJ. NO. IM 089-3(27)
SHEET 13 OF 370 SHEETS