STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 2.30	SQUARE STEEL (in) 2.0 lb/ft 2.65	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
	NB I-89 MAINLINE																																		
NB 106.899	BRIDGE 86-2 I-89	1	6"	8"	.33						1	~~X~~	9		X			1																VD-701		E-134
NB 107.000	MILE 107	1	12"	48"	4						1			X 36			X	1																D10-3		E-139
NB 107.110	BRIDGE 85-3 I-89	1	6"	8"	.33						1	~~X~~	9		X			1																VD-701		E-134
NB 107.050	St. Albans 8 / Swanton 17	1	156"	54"		58.5					2												2			351 X								J1	
NB 107.195 LT		1	36"	36"	9						2			X 90			X	2																R3-4		E-143
NB 107.195 RT.	BRIDGE VERTE BEFORE ROAD	1	48"	48"	16						2									~~X~~			2	214.7 X										VW-005		E-150
NB 107.245	NARROW BRIDGE	1	36"	36"	9						2			X 84			X	2																W5-2		E-154
NB 107.320 LT		1	12"	36"	3						1			X 30			X	1																OM-3		E-120
NB 107.320 RT.		1	12"	36"	3						1			X 30			X	1																OM-3		E-120
NB 107.460 RT.	BRIDGE 86-N I-89	1	6"	8"	.33						1	~~X~~	9		X			1																VD-701		E-134
NB 107.590 LT		1	36"	36"	9						2			X 84			X	2																R3-4		E-143
NB 107.906 LT.		1	36"	36"	9						2			X 90			X	2																R3-4		E-143
NB 108.000	MILE 108	1	12"	48"	4						1			X 36			X	1																D10-3		E-139
NB 109.000	MILE 109	1	12"	48"	4						1			X 36			X	1																D10-3		E-139
NB 109.030	BRIDGE 86-2-N I-89	1	6"	8"	.33						1	~~X~~	9		X			1																VD-701		E-134
												LB ~~35.84~~	LB 36	LB ~~483~~ 516	LB 35.84	LB	LB 483	EA 17	LB	LB ~~31.2~~	LB	LB		LB 214.7	LB	LB ~~291.6~~ 351	LB								
	TOTALS				SF 71.32	SF 58.5	EA.	SF				LB ~~518.84~~ 552			LB 518.84					LB ~~31.2~~			EA. 2	LB ~~291.6~~ 565.7				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: GEORGIA-FAIRFAX	PROJECT NO.: IM-089-3 (26)
DESIGN FILE NAME: IR089-3.DGN	
IPARM FILE NAME: /TRAF/JHK/Tr089tsl.1	PLOT DATE: 10-JUL-1997
SURVEYED BY:	SURVEY DATE:
SQUAD LEADER: ABK	DRAWN BY: JHK
TRAFFIC SHEET NO. 6 OF 14	SHEET: 36 OF 121