STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 2.30	SQUARE STEEL (in) 2.0 lb/ft 2.65	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	STRAIN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
	NB I-89 MAINLINE CONT.																																		
NB 109.207	REST ~~PARKING~~ AREA 1 MILE	1	120"	60"		50					2												2				X 350.4							13	
NB 109.210	BRIDGE B6-3-N I-89	1	6"	8"	.33						1	X			X			1																VD-701		E-134
NB 109.707	REST ~~PARKING~~ AREA 1/2 MILE	1	120"	60"		50					2												2				X 365							13	
NB 110.000	MILE 110	1	12"	48"	4						1			X 36			X	1																D10-3		E-139
NB 110.240		1	18"	18"	2.25						1			X 30			X	1																OM-1		E-150
NB 110.247	REST ~~PARKING AREA~~	1	78"	78"		42.25					2												2		X 261										
NB 110.340	BRIDGE B6-4-N I-89	1	6"	8"	.33						1	X			X			1																VD-701		E-134
NB 110.369		1	48"	48"	16						2									~~X~~			2		209									W4-1		E-150
NB 110.422 L1	ONE WAY	1	36"	12"	3						1			X 36			X	1																R6-1R		E-142
NB 110.834	ENTERING TOWN OF FAIRFAX	1	36"	24"	6						1			X 42			X	1																		E-131
NB 111.000	MILE 111	1	12"	48"	4						1			X 36			X	1																D10-3		E-139
NB 111.50 LT. & RT.		2	36"	36"	18						4			168																						
NB 107.35 LT. & RT.		2	48"	48	32						4			219																						
												LB ~~17.92~~	LB 18	LB ~~168~~ 567	LB 17.92	LB	LB 168	EA 7	LB	LB 36.4	LB	LB		LB	LB 162	LB	LB 580								
	TOTALS				SF ~~35.91~~ 85.91	SF 142.25	EA.	SF				LB ~~185.92~~ 585.0			LB 185.92					LB 36.4			EA. 6	LB 742				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: GEORGIA-FAIRFAX	PROJECT NO.: IM-089-3 (26)
DESIGN FILE NAME: /TRAF/JHK/IR089-3.DGN (PARM FILE NAME: /TRAF/JHK/Ir089ts2.) SURVEYED BY: SQUAD LEADER: ABK TRAFFIC SHEET NO. 7 OF 14	PLOT DATE: 16-MAY-1997 SURVEY DATE: DRAWN BY: JHK SHEET: 37 OF 121