STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 2.30	SQUARE STEEL (in) 2.0 lb/ft 2.65	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	STRONG REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
	SB I-89 MAINLINE																																		
SB 111.000	MILE 111	1	12"	48"	4						1			X 36			X	1																D10-3		E-139
SB 110.919		1	48"	48"	16						2									~~X~~			2	23.8										W4-1		E-150
SB 110.941	ENTERING TOWN OF GEORGIA	1	36"	24"	6						1			X 42			X	1																		E-131
SB 110.883 LT.	ONE WAY	1	36"	12"	3						~~1~~ 2			X 84			X	1																R6-1R		E-142
SB 110.000	MILE 110	1	12"	48"	4						1			X 36			X	1																D10-3		E-139
SB 109.000	MILE 109	1	12"	48"	4						1			X 36			X	1																D10-3		E-139
SB 108.000	MILE 108	1	12"	48"	4						1			X 36			X	1																D10-3		E-139
SB 107.914 LT.		1	36"	36"	9						~~1~~ 2			X 48			X	1																R3-4		E-143
SB 107.892	EXIT 18	1	96"	30"	20																														E-131
	Milton Fairfax 1 Mile	1	162"	156"		175.5					2																	X		1228.5 ~~1222~~	10X26		SET BOLT TENSION TO 33.129 KIPS	14	
	NEXT EXIT 10 MILES	1	96"	24"	16																														E-131
SB 107.673	BRIDGE FREEZE BEFORE ROAD	1	48"	48"	16						2			X 108						~~X~~														VW-005		E-150
SB 107.598 LT.		1	36"	36"	9						1			X 48			X	1																RD-4		E-143
SB 107.516 RT.		1	12"	36"	3						1			X 36			X	1																OM-3		E-120
												LB	LB	LB 360	LB	LB	LB 360	EA 9	LB	LB 72.8	LB	LB		LB 23.8	LB	LB	LB								
	TOTALS				SF ~~111~~ 114	SF 175.5	EA.	SF				LB ~~360~~ 510			LB 360					LB 72.8			EA. 2	LB				EA. 2	EA.	LB 1229 ~~1222~~					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: GEORGIA-FAIRFAX	PROJECT NO.: IM-089-3 (26)
DESIGN FILE NAME: /TRAF/JHK/IR089-3.DGN	
IPARM FILE NAME: /TRAF/JHK/ir089ts3.I	PLOT DATE: 16-MAY-1997
SURVEYED BY:	SURVEY DATE:
SQUAD LEADER: ABK	DRAWN BY: JHK
TRAFFIC SHEET NO. 9 OF 14	SHEET: 39 OF 121