

QUANTITY SHEET

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES							DETAILED SUMMARY OF QUANTITIES					DETAILED SUMMARY OF QUANTITIES		
QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	REUNDING	QUANTITIES	UNIT	ITEMS	QUANTITIES	UNIT	ITEMS				
1	EA	DEMOLITION AND DISPOSAL OF BUILDING (PARTIAL)	202.10	EST.										
200	CY	UNCLASSIFIED EXCAVATION	203.17											
* 200	CY	SOLID ROCK EXCAVATION	203.16	EST.										
550	CY	EXCAVATION OF SURFACES AND PAVEMENTS	203.28											
50	CY	EARTH BORROW	203.30	EST.										
425	CY	SAND BORROW	203.31											
90	CY	TRENCH EXCAVATION OF EARTH	204.20											
175	CY	SUBBASE DENSE GRADED CRUSHED STONE	301.35	EST.										
7	CWT	EMULSIFIED ASPHALT	404.65	EST.										
400	TON	BITUMINOUS CONCRETE PAVING	406.25	EST.										
1	EA	REHABILITATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.41											
1000	LF	6' UNDERDRAIN	605.10	EST.										
2	EA	UNDERDRAIN FLUSHING BASIN	605.95	EST.										
100	LF	VERTICAL GRANITE CURB	616.21	EST.										
2100	LF	REMOVING AND RESETTING CURB	616.40											
30	SY	BRICK PAVING (CONCRETE GRIS) (MODIFIED)	618.20	3										
475	SY	BRICK PAVING (SOLID PAVERS)	618.20	2										
1	LS	FIELD OFFICE - ENGINEERS	631.10											
1	LS	TESTING EQUIPMENT - CONCRETE	631.16											
1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17											
1	LS	FIELD OFFICE - TELEPHONE	631.25											
1	LS	MOBILIZATION	635.10	EST.										
70	LF	PAINTED CURB	646.27											
2000	LF	4' DURABLE WHITE LINE	646.40	EST.										
2500	LF	4' DURABLE YELLOW LINE	646.41	EST.										
1000	LF	8' DURABLE WHITE LINE	646.42											
2	EA	DURABLE LETTER OR SYMBOL	646.50											
160	SY	GEOTEXTILE FABRIC FOR ROADBED SUBGRADE SEPARATOR	649.11	EST.										
1150	SY	GEOTEXTILE FOR UNDERDRAIN TRENCH LINING	649.41	EST.										
50	LB	SEED	651.15	EST.										
450	SY	SODDING	651.30	EST.										
50	CY	TOPSOIL	651.35											
1	LS	ROADSIDE REST FACILITIES (BLDG. REND)- MAIN BLDG.	658.15											
1	LS	ROADSIDE REST FACILITIES (BLDG. REND)- STORAGE BLDG.	658.15											
90	SF	TRAFFIC SIGNS, TYPE A	675.20	4.6										
575	LB	FLANGED CHANNEL SIGN POST	675.30	17										
15	EA	REMOVING SIGNS	675.50											
50	EA	DELINEATORS WITH STEEL POSTS	676.10											
28	EA	REMOVAL OF EXISTING DELINEATORS	676.12											
* 250	LB	FERTILIZER	651.18	EST.										
* 1	TON	AGRICULTURAL LIMESTONE	651.20	EST.										
* 1	TON	HAY MULCH	651.25	EST.										

* ITEMS OUT OF ORDER

SEEDING FORMULA RURAL AREAS

% WT.	LBS./A.	NAME	PUR %	GERM. %
37.5	22.5	CREeping RED FESCUE	98	85
37.5	22.5	TALL FESCUE	95	90
5.0	3.0	RED TOP	95	90
15.0	9.0	BIRDFOOT TREFOL	98	85
5.0	3.0	ANNUAL RYEGRASS	95	85
100.0	60.0			

GENERAL NOTES

SEED MIXTURE SHALL NOT HAVE A WEED CONTENT EXCEEDING 0.40% BY WEIGHT AND SHALL BE FREE OF ALL NOXIOUS SEED.
SEEDS TO BE APPLIED PER SEEDING FORMULAS OR AS DIRECTED BY THE ENGINEER.

SURVEYED BY _____ DATE _____
 DRAWN BY _____ DATE _____
 SQUAD LEADER _____
 DESIGN FILE NO. _____
 IPARM FILE _____ DATE PLOTTED _____
 PROJ. NAME WATERFORD WELCOME CENTER
 PROJ. NO. 1M-BLDG (3)
 SHEET 2 OF 24 SHEETS