STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

Metric

SUMMARY OF ESTIMATED QUANTITIES

					BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						101500	101500	m2	COLD PLANING - BIT. PAVEMENT	210.10	725
						40	40	t	AGGREGATE SHOULDERS	402.12	2
						6530	6530	kg	EMULSIFIED ASPHALT	404.65	65
						9800	9800	t	BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	406.25	94
						1	1	LS	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	
									*** BEGIN OPTION ITEMS ***		
						12	12	m	JOINT SEALER, HOT POURED	524.11	0.4
						12	12	m	JOINT SEALER, COLD POURED	524.13	0.4
									*** END OPTION ITEMS ***		
						2	2	EA	CHANGING ELEV. OF DROP INLETS, CATCH BASINS OR MANHOLES	604.40	EST.
						2	2	EA	REHABILITATION OF DROP INLETS, CATCH BASINS OR MANHOLES, CLASS I	604.412	EST.
						1	1	EA	REHABILITATION OF DROP INLETS, CATCH BASINS OR MANHOLES, CLASS II	604.415	EST.
						1	1	EA	REHABILITATION OF DROP INLETS, CATCH BASINS OR MANHOLES, CLASS III	604.418	EST.
						86	86	HR	POWER BROOM RENTAL	608.30	EST.
						86	86	HR	POWER BROOM RENTAL (MOD.)	608.30	EST.
						1	1	HR	TRUCK RENTAL (N.A.B.I.)	608.37	EST.
						280	280	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
						820	820	HR	FLAGGERS	630.15	EST.
						1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	
						1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	
						1	1	LS	MOBILIZATION	635.10	
						1	1	LS	TRAFFIC CONTROL	641.10	
						2	2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
						10900	10900	m	100 mm WHITE LINE (MOD.)	646.20	106
						8650	8650	m	100 mm YELLOW LINE (MOD.)	646.21	85
						145	145	m	200 mm WHITE LINE	646.22	10
						10900	10900	m	DURABLE 100 mm WHITE LINE (MOD.)	646.40	106
						8650	8650	m	DURABLE 100 mm YELLOW LINE (MOD.)	646.41	85
						145	145	m	DURABLE 200 mm WHITE LINE	646.42	10
						10900	10900	m	TEMPORARY 100 mm WHITE LINE (MOD.)	646.60	106
						8650	8650	m	TEMPORARY 100 mm YELLOW LINE (MOD.)	646.61	85
						145	145	m	TEMPORARY 200 mm WHITE LINE	646.62	10

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		BITUMINOUS CONCRETE PAVEMENT (PG 58-28)
9614	t	INTERSTATE ROUTE 91, TYPE III WEARING COURSE
46	t	BRIDGE WEARING COURSE, TYPE III
46	t	BRIDGE BASE COURSE, TYPE IV
9706	t	SUBTOTAL
94	t	ROUNDING
9800	t	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

REVISED BY JPC 8/18/97

PROJECT : SHEFFIELD - BARTON	PROJECT NO. : IM 091-3(9)
DESIGN FILE NAME: /pave/97q018/pq018.dgn	
PARM FILE NAME: /pave/97q018/pq018prm	PLOT DATE: 18-AUG-1997
SURVEYED BY: CLD	SURVEY DATE: 4/97
SQUAD LEADER: JAW	DRAWN BY: NLL
	SHEET: 3 OF 6