

COMPOSITE QUANTITY SHEET #1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

HARTFORD-SHARON IM 089-I(57)						SHARON-ROYALTON IM 089-I(58)					TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
EROSION CONTROL	ROADWAY	BRIDGE	TRAINING	FULL C.E.		EROSION CONTROL	ROADWAY	BRIDGE		FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING	QUANTITIES	UNIT	ITEMS
	5						5				10	EA	THINNING AND TRIMMING FOR SIGNS	201.31	-			
	1260						100				1360	CY	COMMON EXCAVATION	203.15	-			
	1										1	CY	SOLID ROCK EXCAVATION	203.16	-			
	75						25				100	CY	EARTH BORROW	203.30	-			
	41500						28500				70000	LF	SHOULDER BERM REMOVAL	203.40	-			
	80										80	CY	TRENCH EXCAVATION OF EARTH	204.20	-			
	1						1				2	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N. A. B. I.)	204.22	-			
	440										440	CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	-			
	284000						245000				529000	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	-			
	126000						107500				233500	LF	MILLED RUMBLE STRIPS	213.10	-			
	700										700	CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	-			
	1700						1250				2950	TON	AGGREGATE SHOULDERS, RAP	402.13	-			
	1200						1200				2400	CWT	EMULSIFIED ASPHALT	404.65	-			
	1						1				2	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N. A. B. I.)	406.50	-			
	41000						35000				76000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	-			
	1						1				2	LU	AIR VOIDS PAY ADJUSTMENT (N. A. B. I.)	490.31	-			
	1						1				2	LU	MAT DENSITY PAY ADJUSTMENT (N. A. B. I.)	490.32	-			
	1						1				2	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N. A. B. I.)	490.33	-			
	1						1				2	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N. A. B. I.)	490.34	-			
		97						650			747	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	-			
		20						100			120	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	-			
	25										25	LF	12" CSP .064 (2-2/3 X 1/2)	601.0005	-			
	1										1	EA	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18	-			
							1				1	EA	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-			
	31						42				73	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-			
	4						5				9	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-			
	4						5				9	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	-			
	160										160	LF	6 INCH UNDERDRAIN PIPE	605.10	-			
	340						275				615	HR	POWER GRADER RENTAL	608.15	-			
	56						10				66	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	-			
	200						180				380	HR	POWER BROOM RENTAL, TYPE I	608.30	-			
	10						10				20	HR	TRUCK RENTAL	608.37	-			
	10						10				20	HR	LOADER RENTAL, TYPE I	608.40	-			
	425						80				505	CY	STONE FILL, TYPE I	613.10	-			
	600										600	LF	BITUMINOUS CONCRETE CURB, TYPE B	616.315	-			
	600										600	LF	REMOVAL OF EXISTING CURB	616.41	-			
	320						58				378	EA	YIELDING MARKER POSTS	619.17	-			

PROJECT NAME: HARTFORD-SHARON / SHARON-ROYALTON
 PROJECT NUMBER: IM 089-I(57) / IM 089-I(58)
 FILE NAME: 97A184.dgn PLOT DATE: 13-AUG-2010
 PROJECT LEADER: CDL DRAWN BY: SJL
 DESIGNED BY: SJL CHECKED BY: EPD
 PLOT FILE: 97A184_3.I SHEET 3 OF 62