STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												1.12	2.0	3.0	1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6								
SOUTHBOUND MM 0.11 RT		1	36	36	9.00						2					X		X														R3-4		SHS
SOUTHBOUND MM 0.85 RT		1	36	36	9.00						2					X		X														R3-4		SHS
SOUTHBOUND MM 1.18 RT		1	36	36	9.00						2					X		X														R3-4		SHS
SOUTHBOUND MM 3.23 RT		1	36	36	9.00						2					X		X														R3-4		SHS
SOUTHBOUND MM 4.23 RT		1	36	36	9.00						2					X		X														R3-4		SHS
SOUTHBOUND MM 6.64 RT		1	36	36	9.00						2					X		X														R3-4		SHS
SOUTHBOUND MM 6.81 LT	BRIDGE 11-S I-89						1				1				X			X																
SOUTHBOUND STA 420+51 (MM 7.99 LT)	BRIDGE 12-S I-89						1				1				X			X														REFER TO SHEET 31 FOR ROADWAY RECONSTRUCTION PLAN		
SOUTHBOUND STA 422+40 (MM 8.00 LT)	MILE 8						~~0~~ 1				~~0~~ 1				~~0~~ X			X														REFER TO SHEET 31 FOR ROADWAY RECONSTRUCTION PLAN RETAIN SIGN		
SOUTHBOUND MM 9.65 RT		1	36	36	9.00						2					X		X														R3-4		SHS
SOUTHBOUND MM 9.67 RT		1	36	36	9.00						2					X		X														R3-4		SHS
EXIT 1 RAMP D STA. 114+09 RT		1	36	36	9.00						2					X		X														W3-1		SHS
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."		SUBTOTAL			81.00							LF	LF	LF	LF 24	LF 270	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
		ROUNDING			0.00																														
		TOTALS			SF 81.00	SF	EA. ~~3~~ 2	SF				LF			LF 294					LB			EA.	LB				EA.	EA.	LB					

TRAFFIC SIGN SUMMARY SHEET

PROJECT NAME: HARTFORD - SHARON
PROJECT NUMBER: IM 089-1(57)

FILE NAME: 97A184.dgn
PROJECT LEADER: CDL
DESIGNED BY: JDM
PLOT FILE: 97A184_27.I

PLOT DATE: 8/6/2010
DRAWN BY: JDM
CHECKED BY: EPD
SHEET 27 OF 62