QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

	FULL E&C	EROSION CONTROL	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				3000	3000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
				2000	2000	HR	FLAGGERS	630.15	EST.
	0.5				0.5	LS	FIELD OFFICE, ENGINEERS	631.10	-
	0.5				0.5	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
	1500				1500	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-
				0.5	0.5	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
				1	1	LS	TRAFFIC CONTROL (IM 089-1(58))	641.10	-
				4	4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
				73000	73000	LF	DURABLE 6 INCH WHITE LINE, RECESSED POLYUREA	646.426	1121
				60000	60000	LF	DURABLE 6 INCH YELLOW LINE, RECESSED POLYUREA	646.436	1250
				2300	2300	LF	DURABLE 12 INCH WHITE LINE, RECESSED POLYUREA	646.466	109
				34	34	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	-
				24	24	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
				146000	146000	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	1962
				119000	119000	LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	1500
				3600	3600	LF	TEMPORARY 12 INCH WHITE LINE, PAINT	646.662	95
				68	68	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	-
				48	48	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
				4500	4500	EA	LINE STRIPING TARGETS	646.76	137
		220			220	SY	GEOTEXTILE UNDER STONE FILL	649.31	3.11
		2			2	LB	SEED	651.15	0.9
		10			10	LB	FERTILIZER	651.18	1
		1			1	TON	AGRICULTURAL LIMESTONE	651.20	0.96
		1			1	TON	HAY MULCH	651.25	EST.
		10			10	CY	TOPSOIL	651.35	-
		120			120	SY	TEMPORARY EROSION MATTING	653.20	-
				115	115	SF	TRAFFIC SIGNS, TYPE A	675.20	1.00
				360	360	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-
				16	16	EA	REMOVING SIGNS	675.50	-
				2	2	EA	ERECTING SALVAGED SIGNS	675.60	-
				549	549	EA	REMOVAL OF EXISTING DELINEATOR	676.12	-
				1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
				549	549	EA	SPECIAL PROVISION (DELINEATOR WITH STEEL POST)	900.620	-
				11	11	EA	SPECIAL PROVISION (REPLACE MANUFACTURED TERMINAL SECTION WOOD POST)	900.620	-
				30	30	EA	SPECIAL PROVISION (TIGHTEN MANUFACTURED TERMINAL SECTION ANCHOR CABLE)	900.620	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: SHARON - ROYALTON
PROJECT NUMBER: IM 089-1(58)

FILE NAME: 97A184.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: 97A184_48.1

PLOT DATE: 13-AUG-2010
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 48 OF 62