STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SUMMARY SHEET 1

BEGIN MILEMARKER	END MILEMARKER	POS.	203.30 EARTH BORROW	203.40 SHOULDER BERM REMOVAL	402.13 AGG. SHOULD. (RAP)	604.40 CHANGE ELEV. OF D.I.	604.412 REHAB. D.I. CLASS I	604.415 REHAB. D.I. CLASS II	604.418 REHAB. D.I. CLASS III	613.10 STONE FILL, TYPE I	621.20 STEEL BEAM G.R. GALV.	621.50 MANUF. TERMINAL SECTION FLARED	621.60 ANCHOR FOR S.B. RAIL	621.72 GRAIL APPROACH SECTION, NETC 2	621.76 REPLACE G.R. POST	621.77 REPLACE G.R. BEAM	621.80 REMOVE & DISP. OF G.R.	649.31 GEOT. UNDER STONE FILL	676.12 REMOVAL OF EXIST. DELIN.	900.620 TYPE I GUARD RAIL ENDS	900.620 TYPE I RAMPS	900.620 TYPE II	900.620 TYPE III	900.620 TYPE I WITH PLAQUE	900.620 TYPE I WITHOUT PLAQUE	900.620 TIGHTEN TERM. SECT. ANCHOR CABLE	900.620 REPLACE TERMINAL SECT. WOOD POST	REMARKS
			CY	FT	TON	EACH	EACH	EACH	EACH	CY	LF	EACH	EACH	EA	EA	EA	LF	SY	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	
SOUTHBOUND																											
12.245	17.505				625	1	24	3	3										264		15	12	9	106	106			ESTIMATED QUANTITIES TO BE USED AS
	RAMP A																											DIRECTED BY RESIDENT ENGINEER
12.250	STA. 0+45.75	OUT		4942											96	68				2						1		REPLACE BEAMS AND POSTS AS NECESSARY
13.276	13.405	OUT	25	545								1			11	10	37.5			1								REPLACE BEAMS AND POSTS AS NECESSARY
																												REPLACE MTS
RAMP A, STA. 5+50		LT								5																		TO BE USED FOR REPAIR OF ERODED AREAS
13.310	13.399	MED		376											7	15				1								REPLACE BEAMS AND POSTS AS NECESSARY
BRIDGE 15 S																												
13.449	13.550	MED		427											8	17				1						1		REPLACE BEAMS AND POSTS AS NECESSARY
13.455	13.578	OUT		520									1		10	9				1						1		REPLACE BEAMS AND POSTS AS NECESSARY
																												REPLACE ANCHOR
13.820	13.849	OUT		123											2	2				1						1		REPLACE BEAMS AND POSTS AS NECESSARY
13.833	13.853	MED		85											2	2				1						1		REPLACE BEAMS AND POSTS AS NECESSARY
BRIDGE 16 S																												
13.943	14.044	OUT		427											8	6				1								REPLACE BEAMS AND POSTS AS NECESSARY
13.946	14.020	MED		313											6	8				1								REPLACE BEAMS AND POSTS AS NECESSARY
14.199	14.291	OUT		389											8	4				2						1		REPLACE BEAMS AND POSTS AS NECESSARY
14.337	14.360	OUT		98											1	2				1						1	1	REPLACE BEAMS AND POSTS AS NECESSARY
14.348	14.365	MED		72											1	1				1						1	1	REPLACE BEAMS AND POSTS AS NECESSARY
BRIDGE 17 S																												
14.540	14.599	OUT		250											5	9												REPLACE BEAMS AND POSTS AS NECESSARY
14.542	14.607	MED		275											6	2												REPLACE BEAMS AND POSTS AS NECESSARY
BRIDGE 18 S																												
14.676	14.716	OUT		169											3	7				1								REPLACE BEAMS AND POSTS AS NECESSARY
14.684	14.754	MED		295										1	6	2				1								REPLACE BEAMS AND POSTS AS NECESSARY
																												REPLACE GUARDRAIL APPROACH
SUBTOTAL			25	9306	625	1	24	3	3	5	-	1	1	1	180	164	37.5	-	264	16	15	12	9	106	106	8	2	

ITEM DETAIL SUMMARY SHEET 1

PROJECT NAME: SHARON - ROYALTON
PROJECT NUMBER: IM 089-1(58)

FILE NAME: 97A184.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: 97A184_49.T

PLOT DATE: 8/6/2010
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 49 OF 62