STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												1.12	2.0	3.0	1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6								
STA. 42+75 RT EXIT 2, RAMP C	WRONG WAY	1	36	24	6.00						2					33.50 X		X															R5-1A		SHS
							1																										MOUNT WITH WRONG WAY SIGN		
STA. 42+75 LT EXIT 2, RAMP C	WRONG WAY	1	36	24	6.00						2																						R5-1A MOUNT WRONG WAY SIGN BACK TO BACK WITH RETAINED GUIDE SIGNS		SHS
MM 14.776 MED SB		1	36	36	9.00						2					28.55 X		X															R3-4		SHS
MM 14.984 MED SB		1	36	36	9.00						2					28.58 X		X															R3-4		SHS
	TOTAL THIS SHEET				30.00		1									90	90.63																		
	TOTAL FROM TSSS 1				39.00		1									120	121.50																		
	TOTAL FROM TSSS 2				45.00											150	146.91																		
												LF	LF	LF	LF	LF 359.04 ~~360~~	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
	SUBTOTAL				114.00																														
	ROUNDING				~~1.00~~																														
	TOTALS				SF 114.00 ~~115.00~~	SF	EA. 2	SF				LF			LF 360					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 3

PROJECT NAME: SHARON - ROYALTON
PROJECT NUMBER: IM 089-1(58)

FILE NAME: 97A184.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: 97A184_59.I

PLOT DATE: 8/6/2010
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 59 OF 62