

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	EROSION CONTROL	BRIDGE 40 N	BRIDGE 40 S	ALTERNATE A (BRIDGE 40 N)	ALTERNATE B (BRIDGE 40 N)	ALTERNATE A (BRIDGE 40 S)	ALTERNATE B (BRIDGE 40 S)	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									1	1		LS	TESTING EQUIPMENT, PROTECTIVE COATINGS	631.18				
									1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
	1560									1560		HR	EMPLOYEE TRANEESHIP	634.10				
1										1		LS	MOBILIZATION/DEMOLIBILIZATION	635.11				
			0.5	0.5						1		LS	TRAFFIC CONTROL	641.10				
2										2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
2										2		EACH	PORTABLE ARROW BOARD	641.16				
2600										2600		LF	DURABLE 6 INCH WHITE LINE, THERMOPLASTIC	646.422				
1300										1300		LF	DURABLE 6 INCH YELLOW LINE, THERMOPLASTIC	646.432				
14920										14920		LF	TEMPORARY 6 INCH WHITE LINE, TYPE II TAPE	646.621				
24890										24890		LF	TEMPORARY 6 INCH YELLOW LINE, TYPE II TAPE	646.631				
1999										1999		EACH	RAISED PAVEMENT MARKERS, TYPE II	646.75				
7080										7080		SF	PAVEMENT MARKING MASK	646.86				
		130								130		SY	GEOTEXTILE UNDER STONE FILL	649.31				
		130								130		SY	GEOTEXTILE FOR SILT FENCE	649.51				
		180								180		LB	SEED	651.15				
		180								180		LB	SEED, WINTER RYE	651.17				
		1500								1500		LB	FERTILIZER	651.18				
		6								6		TON	AGRICULTURAL LIMESTONE	651.20				
		13								13		TON	HAYMULCH	651.25				
85										85		CY	TOPSOIL	651.35				
		1								1		LS	EPSC PLAN	652.10				
		150								150		HR	MONITORING EPSC PLAN	652.20				
		1								1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
		1070								1070		SY	TEMPORARY EROSION MATTING	653.20				
		10								10		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
		80								80		CY	VEHICLE TRACKING PAD	653.35				
		9								9		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
		6200								6200		LF	PROJECT DEMARCATION FENCE	653.55				
88.7										88.7		SF	TRAFFIC SIGNS, TYPE A	675.20				
13										13		LF	FLANGED CHANNEL SIGN POST	675.301				
190										190		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
9										9		EACH	REMOVING SIGNS	675.50				
2										2		EACH	ERECTING SALVAGED SIGNS	675.60				
1										1		EACH	DELINEATOR WITH STEEL POST	676.10				
													BEGIN ALTERNATE ZA					
					607		607			1214		CY	SPECIAL PROVISION (HP CONCRETE, CLASS A LOW CEMENT) (FPQ)	900.608				
						607		607		1214		CY	SPECIAL PROVISION (HP CONCRETE, CLASS A LOW CEMENT) (SIPCMF) (FPQ)	900.608				
													END ALTERNATE ZA					
8										8		EACH	SPECIAL PROVISION (GR APPROACH SECTION TO F-SHAPE CONCRETE RAIL)	900.620				