STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																										
NORTHBOUND 71.28 RT	KEEP RIGHT EXCEPT TO PASS	1	1200	1500	1.80						2												2	99.89 X									VR-132		E-141
NORTHBOUND 71.50 RT	EXIT 12	1	2400	750	1.80																													E-131	
	to 5 Wilder	1	2895	3350		9.70					2																	2		~~316.71~~ ~~324~~	W200 X 27		BOLT TENSION 102.75 KN 1 MODIFIED FOUNDATION	60	E-136A
NORTHBOUND 71.99 RT	BRIDGE 45-N I-91	1	150	200	0.03						1		3.05 X																				VD-701		E-134
NORTHBOUND 72.00 RT	MILE 72	1	300	900	0.27						1			3.66 X																				D10-2		E-139
NORTHBOUND 72.20 LT		1	900	900	0.81						2			8.53 X																				R3-4		E-143
NORTHBOUND 72.22 RT	EMERGENCY STOPPING ONLY	1	1200	900	1.08						2			9.14 X																				R8-7		E-142
NORTHBOUND 72.29 RT	NORTH	1	750	375	0.28																													M3-1		E-135
	INTERSTATE 91	1	900	900	0.81																													M1-1		E-135
	EISENHOWER INTERSTATE SYSTEM	1	900	900	0.81						1												1	54.24 X									M1-10		E-135
NORTHBOUND 72.39 RT		1	1200	1200	1.44																													VW-397	78	
	GROOVED SHOULDER	1	600	450	0.27						2			10.82 X																				VP-396	78	
											m	m 3.05 2.5	m 32.15 32	m	m	m		EA	kg	kg	kg		kg 195.0	kg	kg	kg								
TOTALS			m² 9.40	m² 9.70	EA.	m²					m ~~35.2~~ ~~34.5~~			m					kg	EA. 3	kg ~~154.13~~ ~~195.0~~				EA. 2	EA.	kg ~~316.71~~ ~~324~~							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: M:\Projects\99a046\Construction\99a046.dgn 05-JUN-2013 16:0
PROJECT LEADER: J.W TUCKER
DESIGNED BY:
DRAWN BY: S.J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 84 OF 180