STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (mm)	SIGN DIMENSIONS HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS (OPTION ITEMS): FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44, kg/m 3.4	SQUARE STEEL 50, kg/m 3.9	SQUARE STEEL 63, kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75, kg/m 1.9	TUBULAR ALUMINUM 100, kg/m 2.5	TUBULAR ALUMINUM 100 MOD, kg/m 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75, kg/m 11.3	TUBULAR STEEL 89, kg/m 13.4	TUBULAR STEEL 100, kg/m 16.1	TUBULAR STEEL 125, kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL MASS KG	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
NORTHBOUND 75.23 LT		1	900	900	0.81						2			X																			R3-4		E-143
NORTHBOUND 75.44 RT	BRIDGE 48-2 I-91																																		
NORTHBOUND 75.37 RT		1	1200	1200	1.44																												VW-397	78	
	GROOVED SHOULDER	1	600	450	0.27						2			X																			VP-396	78	
NORTHBOUND 75.46 RT	SPEED LIMIT 65	1	1200	1500	1.80																												R2-1		E-142
	MINIMUM 40	1	1200	1200	1.44						2												2	X									VR-141		E-142
NORTHBOUND 75.68 RT	Thetford 8 / St Johnsbury 54	1	4570	1220		5.58					2												2		X									64	
NORTHBOUND 75.83 RT	BRIDGE 49-N I-91	1	150	200	0.03						1		X																				VD-701		E-134
NORTHBOUND 75.93 LT-RT	KEEP RIGHT EXCEPT TO PASS	2	1200	1500	3.60						4												4	X										78	
NORTHBOUND 76.00 RT	MILE 7 6	1	300	900	0.27						1			X																			D10-2		E-139
NORTHBOUND 76.12 LT		1	900	900	0.81						2			X																			R3-4		E-143
NORTHBOUND 77.00 RT	MILE 7 7	1	300	900	0.27						1			X																			D10-2		E-139
NORTHBOUND 76.66 RT	BRIDGE 49-2 I-91																																		
NORTHBOUND 77.07 RT	BRIDGE 50-N I-91	1	150	200	0.03						1		X																				VD-701		E-134
NORTHBOUND 78.00 RT	MILE 7 8	1	300	900	0.27						1			X																			D10-2		E-139
NORTHBOUND 78.31 LT		1	900	900	0.81						2			X																			R3-4		E-143
												m	m 5.0	m 46.0	m	m	m		EA	kg	kg	kg		kg 316.4	kg 100.5	kg	kg								
TOTALS					m² 11.85	m² 5.58	EA.	m²				m 51.0			m					kg			EA. 8	kg 416.9				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: M:\Projects\99a046\Construc PLOT DATE: 05-JUN-2013 16:0
PROJECT LEADER: J.W TUCKER
DRAWN BY: S.J BIJOLLE
DESIGNED BY:
CHECKED BY: J.D. AUSTIN
SHEET 87 OF 180