STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS (OPTION ITEMS) FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
NORTHBOUND 91.53 RT	BRIDGE 56-N I-91	1	150	200	0.03						1		X																				VD-701		E-134
NORTHBOUND 91.90 RT	EMERGENCY STOPPING ONLY	1	1200	900	1.08						2			X																			R8-7		E-142
NORTHBOUND 91.98 RT	NORTH	1	750	375	0.28																												M3-1		E-135
	INTERSTATE 91	1	900	900	0.81																												M1-1		E-135
	EISENHOWER INTERSTATE SYSTEM	1	900	900	0.81						1												1	X									M1-10		E-135
NORTHBOUND 91.88 LT		1	900	900	0.81						2			X																			R3-4		E-143
NORTHBOUND 92.07 RT		1	1200	1200	1.44																												VW-397	78	
	GROOVED SHOULDER	1	600	450	0.27						2			X																			VP-396	78	
NORTHBOUND 92.00 RT	MILE 9 2	1	300	900	0.27						1			X																			D10-2		E-139
NORTHBOUND 92.17 RT	SPEED LIMIT 65	1	1200	1500	1.80																												R2-1		E-142
	MINIMUM 40	1	1200	1200	1.44						2												2	X									VR-141		E-142
NORTHBOUND 92.80 RT	BRIDGE 56-5 I-91																																		
NORTHBOUND 92.39 RT	Bradford 8 St Johnsbury 38	1	4570	1220		5.58					2												2			X								69	
NORTHBOUND 92.64 LT-RT	KEEP RIGHT EXCEPT TO PASS	2	1200	1500	3.60						4												4	X										78	
NORTHBOUND 93.00 RT	MILE 9 3	1	300	900	0.27						1			X																			D10-2		E-139
												m	m 2.5	m 35.0	m	m	m		EA	kg	kg	kg		kg 406.8	kg	kg 144.9	kg								
TOTALS					m2 12.91	m2 5.58	EA.	m2				m 37.5			m					kg			EA. 7	kg 551.7				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)
FILE NAME: M:\Projects\99a046\Construc PLOT 99A046.dgn 05-JUN-2013 16:0
PROJECT LEADER: J.W TUCKER
DRAWN BY: S.J BIJOLLE
DESIGNED BY:
CHECKED BY: J.D. AUSTIN
SHEET 92 OF 180