STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL MASS KG	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
														OPTION ITEMS																						
NORTHBOUND 100.60 RT	BRIDGE 62 I-91	1	150	200	0.03						1		X																				VD-701		E-134
NORTHBOUND 101.00 RT	MILE 101	1	300	1200	0.36						1			X																		D10-3		E-139
NORTHBOUND 101.71 RT	ENTERING TOWN OF NEWBURY	1	900	600	0.54						2			X																				E-131
NORTHBOUND 102.00 RT	MILE 102	1	300	1200	0.36						1			X																		D10-3		E-139
NORTHBOUND 99.45 RT	BRIDGE 62 I-91																																	
NORTHBOUND 102.98 LT		1	900	900	0.81						2			X																		R3-4		E-143
NORTHBOUND 103.00 RT	MILE 103	1	300	1200	0.36						1			X																		D10-3		E-139
NORTHBOUND 103.49 RT	BRIDGE 63-N I-91	1	150	200	0.03						1		X																			VD-701		E-134
NORTHBOUND 104.00 RT	MILE 104	1	300	1200	0.36						1			X																		D10-3		E-139
NORTHBOUND 101.14 RT 103.42 RT	BRIDGE 62-I I-91 BRIDGE 63-N I-91																																	
NORTHBOUND 104.02 LT		1	900	900	0.81						2			X																		R3-4		E-143
NORTHBOUND 105.00 RT	MILE 105	1	300	1200	0.36						1			X																		D10-3		E-139
NORTHBOUND 105.42 LT		1	900	900	0.81						2			X																		R3-4		E-143
NORTHBOUND 105.87 RT	BRIDGE 64-N I-91	1	150	200	0.03						1		X																			VD-701		E-134
NORTHBOUND 105.78	BRIDGE 63-IN I-91																																	
NORTHBOUND 106.00 RT	MILE 106	1	300	1200	0.36						1			X																		D10-3		E-139
NORTHBOUND 107.00 RT	MILE 107	1	300	1200	0.36						1			X																		D10-3		E-139
												m	m 7.5	m 48.0	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg							
TOTALS			m² 5.58	m²	EA.	m²						m 55.5			m					kg			EA.	kg				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: M:\Projects\99a046\Construction\99a046.dgn PLOT DATE: 05-JUN-2013 16:0
PROJECT LEADER: J.W TUCKER DRAWN BY: S.J BIJOLLE
DESIGNED BY: CHECKED BY:
SHEET 96 OF 180