STATE OF VERMONT AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUND-ATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
NORTHBOUND 110.93 RT	SPEED LIMIT 65	1	1200	1500	1.80																												R2-1		E-142
	MINIMUM 40	1	1200	1200	1.44						2												2	X									VR-141		E-142
NORTHBOUND 110.99 RT	ENTERING TOWN OF RYEGATE CALEDONIA CO.	1	900	750	0.68						2			X																					E-131
NORTHBOUND 111.00 RT	MILE 111	1	300	1200	0.36						1			X																			D10-3		E-139
NORTHBOUND 111.14 RT	Barnet 12 / St Johnsbury 19	1	4570	1220		5.58					2												2		X									74	
NORTHBOUND 111.39 RT-LT	KEEP RIGHT EXCEPT TO PASS	2	1200	1500	3.60						4												4	X										78	

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

												m	m	m	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
														12.0										237.3	87.1										
SHEET TOTALS		7.88	5.58									12.0											8	324.1											
		m2	m2	EA.	m2							m			m					kg			EA.	kg				EA.	EA.	kg					
NB TOTALS		171.41	553.17									727.5											66	3797.90				62	6	13558.0					

PROJECT NAME: HARTFORD-NEWBURY

PROJECT NUMBER: IM 091-2(69)

FILE NAME: M:\Projects\99a046\Construction\PLOT99A046.dgn PLOT DATE: 05-JUN-2013 16:0

PROJECT LEADER: J.W TUCKER DRAWN BY: S.J BIJOLLE

DESIGNED BY: CHECKED BY: J.D. AUSTIN

SHEET 99 OF 180