STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL MASS KG	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
SOUTHBOUND 79.00 RT	MILE 79	1	300	900	0.27						1			X																			D10-2		E-139
SOUTHBOUND 80.00 RT	MILE 80	1	300	900	0.27						1			X																			D10-2		E-139
SOUTHBOUND 80.25 RT	Ompompanoosuc River	1	2440	1065		2.60					2												2		X								66	
SOUTHBOUND 80.25 RT	BRIDGE 51-S I-91	1	150	200	0.03						1		X																			VD-701		E-134
SOUTHBOUND 80.30 LT		1	900	900	0.81						2			X																			R3-4		E-143
SOUTHBOUND 80.44 RT	BRIDGE ICES BEFORE ROAD	1	1200	1200	1.44						2			X																			WB-13		E-150
SOUTHBOUND 81.00 RT	MILE 81	1	300	900	0.27						1			X																			D10-2		E-139
SOUTHBOUND 81.53 RT	ENTERING TOWN OF NORWICH WINDSOR CO.	1	900	750	0.68						2			X																					E-131
SOUTHBOUND 82.00 RT	MILE 82	1	300	900	0.27						1			X																			D10-2		E-139
SOUTHBOUND 82.41 LT		1	900	900	0.81						2			X																			R3-4		E-143
SOUTHBOUND 83.00 RT	MILE 83	1	300	900	0.27						1			X																			D10-2		E-139
SOUTHBOUND 83.12 LT-RT	KEEP RIGHT EXCEPT TO PASS	2	1200	1500	3.60						4												4	X									78	
SOUTHBOUND 83.23 RT	BRIDGE 52 I-91	1	150	200	0.03						1		X																			VD-701		E-134
SOUTHBOUND 83.37 RT	Norwich 9 White River Jct 13	1	4725	1220		5.76					2												2			X							66	
												m	m 5	m 58.5	m	m	m		EA	kg	kg	kg		kg 226	kg 134	kg 185.2	kg							
TOTALS					m² 8.75	m² 8.36	EA.	m²				m 63.5			m					kg			EA. 8		kg 545.2			EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: _____ PLOT DATE: 05-JUN-2013 16:0
PROJECT LEADER: J.W TUCKER DRAWN BY: S.J BIJOLLE
DESIGNED BY: _____ CHECKED BY: J.D. AUSTIN
SHEET 106 OF 180