STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
																				OPTION ITEMS															
SOUTHBOUND 100.65 RT	BRIDGE 62 I-91	1	150	200	0.03						1		X																				VD-701		E-134
SOUTHBOUND 100.73 RT	PARKING AREA 1/2 MILE	1	3810	1525		5.81					2												2		X								71	
SOUTHBOUND 101.00 RT	MILE 101	1	300	1200	0.36						1			X																		D10-3		E-139
SOUTHBOUND 101.19 RT	PARKING AREA 1 MILE	1	3810	1525		5.81					2												2			X							71	
101.71 RT	ENTERING TOWN OF BRADFORD	1	900	600	0.54						2			X																			E-131
SOUTHBOUND 102.00 RT	MILE 102	1	300	1200	0.36						1			X																		D10-3		E-139
SOUTHBOUND 102.99 LT	R3-4	1	900	900	0.36						2			X																		R3-4		E-139
SOUTHBOUND 103.00 RT	MILE 103	1	300	1200	0.81						1			X																		D10-3		E-143
SOUTHBOUND 103.51 RT	BRIDGE 63-S I-91	1	150	200	0.03						1		X																			VD-701		E-134
SOUTHBOUND 104.00 RT	MILE 104	1	300	1200	0.36						1			X																		D10-3		E-139
SOUTHBOUND 104.03 LT	R3-4	1	900	900	0.81						2			X																		R3-4		E-143
SOUTHBOUND 105.00 RT	MILE 105	1	300	1200	0.36						1			X																		D10-3		E-139
SOUTHBOUND 105.46 LT	R3-4	1	900	900	0.81						2			X																		R3-4		E-143
SOUTHBOUND 105.83 RT 103.47 RT	BRIDGE 63-S I-91 BRIDGE 63-S I-91																																		
SOUTHBOUND 105.89 RT	BRIDGE 64-S I-91	1	150	200	0.03						1		X																			VD-701		E-134
SOUTHBOUND 106.00 RT	MILE 106	1	300	1200	0.36						1			X																		D10-3		E-139
												m	m 7.5	m 54.0	m	m	m		EA	kg	kg	kg		kg	kg 93.8	kg 153	kg							
TOTALS			m² 5.22	m² 11.62	EA.	m²						m 61.5			m					kg			EA. 4	kg 246.8				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: _____ PLOT DATE: 05-JUN-2013 16:08
PROJECT LEADER: J.W TUCKER DRAWN BY: S.J BIJOLLE
DESIGNED BY: _____ CHECKED BY: J.D. AUSTIN
SHEET 114 OF 180