STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL MASS KG	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
											OPTION ITEMS																								
SOUTHBOUND 107.00 RT	MILE 107	1	300	1200	0.36						1			X																		D10-3		E-139
SOUTHBOUND 107.51 LT		1	900	900	0.81						2			X																		R3-4		E-143
SOUTHBOUND 108.00 RT	MILE 108	1	300	1200	0.36						1			X																		D10-3		E-139
SOUTHBOUND 109.00 RT	MILE 109	1	300	1200	0.36						1			X																		D10-3		E-139
SOUTHBOUND ~~109.00 RT~~ 108.96 RT	BRIDGE 65-5 I-91	1	150	200	0.03						1		X																		VD-701		E-134
SOUTHBOUND 109.35 LT-RT	KEEP RIGHT EXCEPT TO PASS	2	1200	1500	3.60						4												4	X									78	
SOUTHBOUND 109.60 RT	Bradford 12 White River Jct 39	1	4725	1220		5.76					2												2			X							72	
SOUTHBOUND 109.81 RT	SPEED LIMIT 65	1	1200	1500	1.80																										R2-1		E-142
	MINIMUM 40	1	1200	1200	1.44						2												2	X								VR-141		E-142
SOUTHBOUND 109.91 RT		1	1200	1200	1.44																										VW-397	78	
	GROOVED SHOULDER	1	600	450	0.27						2			X																		VP-396	78	
SOUTHBOUND 109.98 RT	SOUTH	1	750	375	0.28																										M3-3		E-135
	INTERSTATE 91	1	900	900	0.81						2																				M1-1		E-135
	EISENHOWER INTERSTATE SYSTEM	1	900	900	0.81						1												1	X								M1-10		E-135
SOUTHBOUND 110.01 RT	BRIDGE 65-5 I-91	1	150	200	0.03						1		X																		VD-701		E-134
SOUTHBOUND 110.00 RT	MILE 110	1	300	1200	0.36						1			X																		D10-3		E-139
SOUTHBOUND 110.03 LT		1	900	900	0.81						2			X																		R3-4		E-143
												m	m 2.5	m 40.0	m	m	m		EA	kg	kg	kg		kg 452	kg	kg 153	kg							
TOTALS			m² 13.54	m² 5.76	EA.	m²						m 42.5			m					kg			EA. 9	kg 605				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: _____ PLOT DATE: 05-JUN-2013 16:08
PROJECT LEADER: J.W TUCKER DRAWN BY: S.J BIJOLLE
DESIGNED BY: _____ CHECKED BY: J.D. AUSTIN
SHEET 115 OF 180