STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (mm)	SIGN DIMENSIONS HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44 kg/m 3.4	SQUARE STEEL (mm) 50 kg/m 3.9	SQUARE STEEL (mm) 63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 13.4	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
												OPTION ITEMS																							
SOUTHBOUND PARKING AREA		1	450	450	0.20						1	X																					OM1-1		E-150
SOUTHBOUND PARKING AREA	PARKING AREA ↗	1	2285	1980		4.52					2												2	X										79	
SOUTHBOUND PARKING AREA	PROHIBITED OVERNIGHT CAMPING UNATTENDED VEHICLES COMMERCIAL ENTERPRISES	1	750	600	0.45																												VR-032		E-144
	WRONG WAY	2	900	600	1.08						2			X																			R5-1A		E-143
SOUTHBOUND PARKING AREA	DO NOT ENTER	2	750	750	1.13						2			X																			R5-1		E-143
SOUTHBOUND PARKING AREA	TRUCKS BUSES ↖	1	600	750	0.45						1			X																				79	
SOUTHBOUND PARKING AREA	CARS ↑	1	600	600	0.36						1			X																				79	
SOUTHBOUND PARKING AREA	PROHIBITED	1	600	900	0.54																												VR-278		E-144
	ALL DOGS MUST BE ON LEASH	1	600	600	0.36						1			X																			VR-648		E-144
SOUTHBOUND PARKING AREA	RESERVED PARKING	1	300	450	0.14						1	X																					R7-8M	78	
SOUTHBOUND PARKING AREA	SAFETY BELTS REQUIRED	1	600	750	0.45						1			X																				78	
SOUTHBOUND PARKING AREA		1	750	750	0.56						1		X																				R3-2		E-143
SOUTHBOUND PARKING AREA	ONE WAY	1	900	300	0.27						2		X																				R6-1R		E-142
SOUTHBOUND PARKING AREA		1	1200	1200	1.44						2			X																			W4-1R		E-150
												m	m	m	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
												2.0	12.0	44.0										90.4											
TOTALS					7.43 m^2	4.52 m^2	EA.	m^2				58.0 m			m					kg			2 EA.	90.4 kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)
FILE NAME:
PROJECT LEADER: J. W TUCKER
DESIGNED BY:
PLOT DATE: 12/14/2005
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN