STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FURNISHED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
INT #11 RAMP A MM. 2.807 LT		1	450	450	0.20						1	X																					OM1-1		E-150
INT #11 RAMP A STA. 0+160 RT & LT	YIELD	2	900	900	1.62						2			X																			R1-2		E-146
INT #11 RAMP A STA. 0+220 RT	PROHIBITED PEDESTRIANS BICYCLISTS STOPPING FOR RECORDING PURPOSES BICYCLES FARM MACHINERY SNOW VEHICLES	1	900	900	0.81																												VR-046		E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	900	900	0.81						2			X																				VR-002		E-142
INT #11 RAMP A STA. 0+260 RT		1	750	750	0.56																												W1-2R		E-151
	30 M. P. H.	1	450	450	0.20						2			X																				W13-1		E-155
INT #11 RAMP A STA. 0+460 RT		1	750	750	0.56						1			X																				R3-2		E-143
INT #11 RAMP A STA. 0+476 LT	ONE WAY	1	900	300	0.27						2		X																					R6-1R		E-142
INT #11 RAMP B MM. 70.44 RT	EXIT 30 M.P.H.	1	1200	1500	1.80						2												2	X									W13-2		E-150
INT #11 RAMP B MM. 70.38		1	450	450	0.20						1	X																					OM1-1		E-150
INT #11 RAMP B MM. 70.37	EXIT 11	1	1800	1500		2.70					2												2	X											E-131
INT #11 RAMP B STA. 0+280 RT		1	750	750	0.56																												W1-2L		E-151
	30 M. P. H.	1	450	450	0.20						2			X																				W13-1		E-155
INT #11 RAMP B STA. 0+340 RT		1	900	900	0.81						2			X																				W3-1A		E-150
INT #11 RAMP B STA. 0+400 RT	NORTH TO SOUTH	1 1 1	600 600 600	300 300 300	0.18 0.18 0.18																												M3-1 M4-5 M3-3		E-136A
	5 4 5	1 1 1	600 600 600	600 600 600	0.36 0.36 0.36																												M1-4		E-136A
	← ← →	1 1 1	525 525 525	375 375 375	0.20 0.20 0.20						2												2	X									X	M6-1 M6-1 M6-1		E-136A
					m²	m²	EA.	m²				m			m					EA	kg			EA.	kg				EA.	EA.	kg				
												4	8.0	44											271.2										
	TOTALS				10.82	2.70						56.0												6										

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S 'SIGN POST DESIGN GUIDELINE.'

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS04.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 01/18/2006
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 120 OF 180

...\DATA\za046TS04.dgn 01/18/2006 11:04:33 AM