STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
INT #13 US 5 MM 0.846 LT	DO NOT PASS	1	600	750	0.45						1			X																			R4-1		E-141
INT #13 US 5 MM 0.980 RT	ONLY	1	900	750	0.68						2			X																			VR-922		E-145A
INT #13 US 5 MM 1.06 LT	EAST	1	600	300	0.18																											M3-2 SIGNS FOR RAMP D		E-136B
	SOUTH	1	600	300	0.18																											M3-3		E-136A
	NORTH	1	600	300	0.18																											M3-1		E-136A
	VERMONT 10A	1	600	600	0.36																											M1-6B		E-136B
	5	1	600	600	0.36																											M1-4C		E-136A
	5	1	600	600	0.36																											M1-4C		E-136A
	←	1	525	375	0.20																											M6-1L		E-136B
	↑	1	525	375	0.20																											M6-3		E-136A
	→	1	525	375	0.20						2													2	X							*3 M6-1R		E-136A
INT #13 US 5 MM 1.06 RT	TO	1	600	300	0.18																											M4-5		E-135
	SOUTH	1	600	300	0.18																											M3-3		E-135
	NORTH	1	600	300	0.18																											*1 M3-1		E-135
	INTERSTATE 91	1	600	600	0.36																											M1-1B		E-135
	INTERSTATE 91	1	600	600	0.36																											M1-1B		E-135
	↑	1	525	375	0.20																											M6-3		E-135
	→	1	525	375	0.20																											M6-1R		E-135
	NORTH	1	600	300	0.18																											M3-1		E-136A
	EAST	1	600	300	0.18																											*2 M3-2		E-136B
	5	1	600	600	0.36																											M1-4		E-136A
	VERMONT 10A	1	600	600	0.36																											M1-6B		E-136B
	←	1	525	375	0.20																											M6-1L		E-136A
	→	1	525	375	0.20						2													2	X							*1 M6-1R		E-136B
												m	m	m 12.0	m	m	m	EA	kg	kg	kg		kg 180.8	kg	kg	kg									
TOTALS		m² 6.49	m²	EA.	m²							m 12.0			m				kg			EA. 4		kg 180.8			EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: M:Projectsca046\Design\da0416TS07 PLOT DATE: 05-JUN-2013 16:0
PROJECT LEADER: RLT DRAWN BY: NHP
DESIGNED BY: ROADWAY DESIGN CHECKED BY: AJB
SHEET 120D OF 180