STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
INT #14 VT 113 MM 6.94 RT	TO EAST WEST	1	600	300	0.18																													M4-5		E-136A
		1	600	300	0.18																													M3-2 SIGNS FOR RAMP C		E-136B
		1	600	300	0.18																													M3-4		E-136B
	5 VERMONT 113 VERMONT 113	1	600	600	0.36																													M1-4C		E-136A
		1	750	600	0.45																													M1-6B		E-136B
		1	750	600	0.45																													M1-6B		E-136B
	← ← →	1	525	375	0.20																													M6-1L		E-136A
		1	525	375	0.20																													M6-1L		E-136B
		1	525	375	0.20						2													2	X								*3	M6-1R		E-136B
#14 VT 114 MM 6.94 RT RAMP A	SOUTH	1	600	300	0.18																													M3-3		E-135
	INTERSTATE 91	1	600	600	0.36																													M1-1B		E-135
	←	1	525	375	0.20						1			X																				M6-1L		E-135
#14 VT 113 MM 7.148 LT RAMP D	NORTH	1	600	300	0.18																													M3-1		E-135
	INTERSTATE 91	1	600	600	0.36																													M1-1B		E-135
	←	1	525	375	0.20						1			X																				M6-1L		E-135
INT #14 VT 113 MM 7.148 LT	WEST EAST TO	1	600	300	0.18																													M3-4 SIGNS FOR RAMP B		E-136B
		1	600	300	0.18																													M3-2		E-136B
		1	600	300	0.18																													M4-5		E-136A
	VERMONT 113 VERMONT 113 5	1	750	600	0.45																													M1-6B		E-136B
		1	750	600	0.45																													M1-6B		E-136B
		1	600	600	0.36																													M1-4C		E-136A
	← → →	1	525	375	0.20																													M6-1L		E-136B
		1	525	375	0.20						2													2	X								*3	M6-1R		E-136B
		1	525	375	0.20																													M6-1R		E-136A

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

											m	m	m	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg									
													8.0											180.8											
TOTALS	m² 6.28	m²	EA.	m²		m 8.0		m			kg	EA. 4	kg 180.8				EA.	EA.	kg																	

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: M:Projectsca046\Design\da0416TS07 PLOT DATE: 05-JUN-2013 16:08
PROJECT LEADER: RLT DRAWN BY: NHP
DESIGNED BY: ROADWAY DESIGN CHECKED BY: AJB
SHEET 120G OF 180