STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 1.7	50 3.4	63 3.9	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) kg/m FOUNDATION	75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INT #16 VT 25 MM 1.02 LT	NORTH SOUTH TO	1	600	300	0.18																												M3-1 IN RAMP A ISLAND		E-135B
		1	600	300	0.18																												M3-3		E-135B
		1	600	300	0.18																												M4-5		E-136A
	VERMONT 25 VERMONT 25 5	1	600	600	0.36																												M1-6A		E-136B
		1	600	600	0.36																												M1-6A		E-136B
		1	600	600	0.36																												M1-4C		E-136A
		1	525	375	0.20																												M6-1L		E-136B
		1	525	375	0.20																												M6-2R		E-136B
		1	525	375	0.20						2												2	X							*3	M6-2R		E-136A
#16 VT 25 MM 1.02 RT	NORTH	1	600	300	0.18																												M3-1		E-135
	INTERSTATE 91	1	600	600	0.36																												M1-1B		E-135
		1	525	375	0.20						1			X																			M6-1L		E-135
#16 VT 25 MM 1.03 LT MM 1.01 RT	ONLY	2	750	750	1.12						2												2	X									VR-921		E-145A
#16 VT 25 MM 1.180 LT	SOUTH	1	600	300	0.18																												M3-3		E-135
	INTERSTATE 91	1	600	600	0.36																												M1-1B		E-135
		1	525	375	0.20						1			X																			M6-1L		E-135
#16 VT 25 MM 1.18 LT	TO SOUTH NORTH	1	600	300	0.18																												M4-5 SIGNS FOR RAMP C		E-136A
		1	600	300	0.18																												M3-3		E-136B
		1	600	300	0.18																												M3-1		E-136B
	5 VERMONT 25 VERMONT 25	1	600	600	0.36																												M1-4C		E-136A
		1	600	600	0.36																												M1-6A		E-136B
		1	600	600	0.36																												M1-6A		E-136B
		1	525	375	0.20																												M6-1L		E-136A
		1	525	375	0.20																												M6-1L		E-136B
		1	525	375	0.20						2												2	X							*3	M6-1R		E-136B
												m	m	m 8.0	m	m	m		EA	kg	kg	kg		kg 271.2	kg	kg	kg							
TOTALS			m² 6.60	m²	EA.	m²						m 8.0			m						kg			EA. 6	kg 271.2				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: M:Projects\ca046\Design\da0416TS07 PLOT DATE: 05-JUN-2013 16:0
PROJECT LEADER: RLT DRAWN BY: NHP
DESIGNED BY: ROADWAY DESIGN CHECKED BY: AJB
SHEET 120J OF 180