STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
INT #17 US 302 MM 1.766 RT	TO EAST WEST	1	600	300	0.18																												M4-5	SIGNS FOR RAMP C		E-136A
		1	600	300	0.18																												M3-2			E-136A
		1	600	300	0.18																												M3-4			E-136A
	5 302 302	1	600	600	0.36																												M1-4C			E-136A
		1	750	600	0.45																												M1-4E			E-136A
		1	750	600	0.45																												M1-4E			E-136A
		1	525	375	0.20																												M6-1L			E-136A
		1	525	375	0.20																												M6-1L			E-136A
		1	525	375	0.20						2												2	X								*3	M6-1R			E-136A
INT. #17 US 302 MM 1.766 RT	SOUTH	1	600	300	0.18																												M3-3			E-135
	INTERSTATE 91	1	600	600	0.36																												M1-1B			E-135
		1	525	375	0.20						1			X																		M6-1L			E-135
#17 US 302 MM 1.970 LT	NORTH	1	600	300	0.18																												M3-1			E-135
	INTERSTATE 91	1	600	600	0.36																												M1-1B			E-135
		1	525	375	0.20						1			X																		M6-1L			E-135
#17 US 302 MM 1.918 LT	WEST EAST TO	1	600	300	0.18																												M3-4	SIGNS FOR RAMP A		E-136A
		1	600	300	0.18																												M3-2			E-136A
		1	600	300	0.18																												M4-5			E-136A
	302 302 5	1	750	600	0.45																												M1-4E			E-136A
		1	750	600	0.45																												M1-4E			E-136A
		1	600	600	0.36																												M1-4C			E-136A
		1	525	375	0.20																												M6-1L			E-136A
		1	525	375	0.20																												M6-1R			E-136A
		1	525	375	0.20						2												2	X								*3	M6-1R			E-136A
												m	m	m 8.0	m	m	m	EA	kg	kg	kg		kg 180.8	kg	kg	kg									
TOTALS		m² 6.28	m²	EA.	m²							m 8.0			m				kg			EA. 4	kg 180.8				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: M:Projectsca046\Design\da0416TS07 PLOT DATE: 05-JUN-2013 16:0
PROJECT LEADER: RLT DRAWN BY: NHP
DESIGNED BY: ROADWAY DESIGN CHECKED BY: AJB
SHEET 120K OF 180