STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
INT #11 RAMP B STA. 0+540 RT	VA HOSPITAL → WRONG WAY	1 1	1350 900	185 600	0.25 0.54																													R5-1A		E-133 E-143
	← SERVICES →	1	1350	185	0.25																															E-133
	← INFORMATION	1	1350	185	0.25						2			X																					E-133
INT #11 RAMP B STA. 0+460 RT	← WHITE RIVER JCT 2	1	1800	300	0.54																															E-123
	HARTLAND 9 →	1	1800	300	0.54																															E-123
	WINDSOR 14 →	1	1800	300	0.54						2			X																					E-123
INT #11 RAMP B STA. 0+540 LT	WRONG WAY	1	900	600	0.54																													R5-1A		E-143
		1	600	600	0.36						1			X																			R9-4A		E-143
INT #11 RAMP B STA. 0+550 LT	DO NOT ENTER	1	750	750	0.56						1			X																			R5-1		E-143
INT #11 RAMP B END RAMP LT	STOP	1 1	750 600	750 750	0.56 0.45																													R1-1 R4-7		E-143 E-144
	ONE WAY ONE WAY	2	900	300	0.54						1			X																			R6-1L		E-142
INT #11 RAMP B END RAMP RT	STOP DO NOT ENTER	1 1	750 750	750 750	0.56 0.56						1			X																			R1-1 R5-1		E-143 E-143
INT #11 RAMP C MM. 70.05	EXIT 30 M.P.H.	1	1200	1500	1.80						2													2	X									W13-2		E-150
INT #11 RAMP C MM. 70.11		1	450	450	0.20						1	X																						0M1-1		E-150
INT #11 RAMP C MM. 70.12	EXIT 11	1	1800	1500		2.70					2													2	X											E-131
												m 2	m	m 32.0	m	m	m		EA	kg	kg	kg		kg 180.8											
TOTALS					m² 9.04	m² 2.70	EA.	m²				m 34.0			m					kg			EA. 4	kg 180.8				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S 'SIGN POST DESIGN GUIDELINE.'

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS04.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 01/18/2006
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 121 OF 180

...\DGN\za046TS04.dgn 01/18/2006 11:04:50 AM