STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44 kg/m 3.4	SQUARE STEEL (mm) 50 kg/m 3.9	SQUARE STEEL (mm) 63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 13.4	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL MASS KG	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
														OPTION ITEMS																					
INT #11 RAMP C STA. 0+280 RT		1	1200	1200	1.44						2			X																		W4-3L		E-155
INT #11 RAMP D STA. 0+030 RT	PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR HITCHHIKERS ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES	1	900	900	0.81																											VR-046		E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	900	900	0.81						2			X																		VR-002		E-142
INT #11 RAMP D STA. 0+268 RT		1	750	750	0.56						1			X																		R3-2		E-143
INT #11 RAMP D STA. 0+284 LT	ONE WAY	1	900	300	0.27						2		X																			R6-1R		E-142
INT #11 SOUTHBOUND MM. 70.33		1	1200	1200	1.44						2			X																		W4-1R		E-150
INT #11 NORTHBOUND MM. 70.35		1	1200	1200	1.44						2			X																		W4-1R		E-150
INT #11 U.S ROUTE 5 MM. 2.735 RT	JCT	1	525	375	0.20																											M2-1		E-135
	INTERSTATE 91	1	600	600	0.36						1			X																		M1-1		E-135
INT #11 U.S ROUTE 5 MM. 2.735 LT	HARTLAND 9	1	1800	300	0.54																													E-123
	WINDSOR 14	1	1800	300	0.54						2			X																					E-123
												m	m 8.0	m 48.0	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg							
TOTALS			m² 8.41	m²	EA.	m²						m 56.0			m					kg			EA.	kg				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: M:\Projects\99a046\Construction\130452.dgn 05-JUN-2013 16:0
PROJECT LEADER: J.W TUCKER
DESIGNED BY:
DRAWN BY: S.J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 123 OF 180