STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MAUT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
INT #11 U.S ROUTE 5 MM. 2.959		1	600	750	0.45																												R4-7		E-144
		1	600	600	0.36																												R3-2		E-143
		2	450	450	0.41						1			X																		OM1-1		E-150
INT #11 U.S ROUTE 5 MM. 2.965	LEFT LANE MUST TURN LEFT	1	750	750	0.56																												R3-7L		E-140
		1	600	750	0.45																												R4-7		E-144
		2	450	450	0.41						1			X																		OM1-1		E-150
INT #11 U.S ROUTE 5 MM. 2.966 RT		1	1200	1200	1.44						2			X																		W4-3R		E-155
INT #11 U.S ROUTE 5 MM. 2.967		1	600	750	0.45																												R4-7		E-144
		1	600	600	0.36																												R3-2		E-143
		2	450	450	0.41						1			X																		OM1-1		E-150
INT #11 U.S ROUTE 5	SOUTH ↓ / SOUTH TO 91 ↓ 89 EXIT 600 FT. / NORTH 91 ↗ ST. JOHNSBURY	1	3500	2740		9.59																											MOUNT ON OVERHEAD STRUCTURE	75	
		1	3500	2740		9.59																														
		1	3960	2740		10.85																														
INT #11 U.S ROUTE 5 MM. 3.040 LT	ONLY	1	1200	750	0.90						2			X																		VR-934		E-145B
INT #11 U.S ROUTE 5 MM. 3.040 RT	ONLY	1	1200	750	0.90						2			X																		VR-935		E-145B
INT #11 U.S ROUTE 5 MM. 3.041		1	600	750	0.45																												R4-7		E-144
		2	450	450	0.41						1			X																		OM1-1		E-150
												m	m	m 44.0	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS					m² 7.96	m² 30.03	EA.	m²				m 44.0			m					kg			EA.	kg				EA.	EA.	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS04.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:
PLOT DATE: 12/13/2005
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 126 OF 180