STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL MASS KG	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
INT #12 RAMP A MM. 71.~~74~~ 63	EXIT 35 M.P.H.	1	1200	1500	1.80						2												2	X								W13-2		E-150
INT #12 RAMP A MM. 71.75		1	450	450	0.20						1	X																				OM1-1		E-150
INT #12 RAMP A MM. 71.75	EXIT 12	1	1800	1500		2.70					2												2	X										E-131
INT #12 RAMP A STA. 0+140 RT		1	900	900	0.81						2			X																		W3-1A		E-150
INT #12 RAMP A STA. 0+220 RT	TO	1	600	300	0.18																											M4-5		E-136A
	5	1	600	600	0.36																											M1-4		E-136A
		1	525	375	0.20						1			X																		M6-1		E-136A
INT #12 RAMP A STA. 0+360 RT	WRONG WAY / ← CHRISTIAN ST	1 1	1800 900	300 600	0.54 0.54																											R5-1A		E-123 E-143
	WILDER 1 →	1	1800	300	0.54																													E-123
	WHITE RIVER JCT 1 →	1	1800	300	0.54																													E-123
	SERVICES →	1	1350	185	0.25						2			X																				E-133
INT #12 RAMP A STA. 0+360 LT	WRONG WAY	1	900	600	0.54																											R5-1A		E-143
		1	600	600	0.36						1			X																		R9-4A		E-143
INT #12 RAMP A END OF RAMP	STOP / DO NOT ENTER	2 2	750 750	750 750	1.13 1.13																											R1-1 R5-1		E-143
	ONE WAY / ONE WAY	2 2	900 900	300 300	0.54 0.54						2			X																		R6-1L R6-1R		E-142
												m 2	m	m 32	m	m	m		EA	kg	kg	kg		kg 180.8	kg	kg	kg							
TOTALS			m² 10.20	m² 2.70	EA.	m²						m 34			m					kg			EA. 4	kg 180.8				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: M:\Projects\99a046\Construction\130452\130452.dgn 05-JUN-2013 16:0
PROJECT LEADER: J.W TUCKER
DESIGNED BY:
DRAWN BY: S.J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 128 OF 180