STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INT #12 RAMP B STA. 0+030 RT	PROHIBITED PEDESTRIANS MOTORCYCLES STOPPING FOR VEHICLES BICYCLES FARM MACHINERY SNOW VEHICLES	1	900	900	0.81																												VR-046		E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	900	900	0.81						2			X																		VR-002		E-142
INT #12 RAMP B STA. 0+387 RT		1	750	750	0.56						1			X																		R3-2		E-143
INT #12 RAMP B STA. 0+403 LT	ONE WAY	1	900	300	0.27						2		X																				R6-1R		E-142
INT #12 SOUTHBOUND MM. 71.83		1	1200	1200	1.44						2			X																		W4-1R		E-150
INT #12 RAMP C STA. 0+030 RT	PROHIBITED PEDESTRIANS MOTORCYCLES STOPPING FOR VEHICLES BICYCLES FARM MACHINERY SNOW VEHICLES	1	900	900	0.81																												VR-046		E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	900	900	0.81						2			X																		VR-002		E-142
INT #12 RAMP C STA. 0+372 RT		1	750	750	0.56						1			X																		R3-2		E-143
INT #12 RAMP C STA. 0+388 LT	ONE WAY	1	900	300	0.27						2		X																				R6-1R		E-142
INT #12 NORTHBOUND MM. 72.15		1	1200	1200	1.44						2			X																		W4-1R		E-150
INT #12 SOUTHBOUND MM. 72.15	EXIT 35 M.P.H.	1	1200	1500	1.80						2												2	X								W13-2		E-150
INT #12 RAMP D MM. 72.18		1	450	450	0.20						1	X																				OM1-1		E-150
INT #12 RAMP D MM. 72.17	EXIT 12	1	1800	1500		2.70					2												2	X										E-131
INT #12 RAMP D STA. 0+120 RT		1	900	900	0.81						2			X																		W3-1A		E-150
												m 2	m 16	m 48.0	m	m	m		EA	kg	kg	kg		kg 180.8	kg	kg	kg								
TOTALS					m² 10.59	m² 2.70	EA.	m²				m 66.0			m					kg			EA. 4	kg 180.8				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS04.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 01/18/2006
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 129 OF 180

...\USA\za046TS04.dgn 01/18/2006 11:05:53 AM