STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																										
INT #12 RAMP D STA. 0+180 RT	TO	1	600	300	0.18																													M4-5		E-136A
	5	1	600	600	0.36																													M1-4		E-136A
	←	1	525	375	0.20						1			X																			M6-1		E-136A
INT #12 RAMP D STA. 0+300 RT	CHRISTIAN ST → WRONG WAY	1	1800	300	0.54																															E-123
		1	900	600	0.54																													R5-1A		E-143
	← WILDER	1	1800	300	0.54																															E-123
	← WHITE RIVER JCT 1	1	1800	300	0.54																															E-123
	← SERVICES	1	1350	185	0.25						2			X																					E-133
INT #12 RAMP D STA. 0+300 LT	WRONG WAY	1	900	600	0.54																													R5-1A		E-143
		1	600	600	0.36						1			X																			R9-4A		E-143
INT #12 RAMP D END OF RAMP	STOP / DO NOT ENTER	2	750	750	1.13																													R1-1		E-143
		2	750	750	1.13																													R5-1		
	ONE WAY / ONE WAY	2	900	300	0.54						2			X																			R6-1L		E-142
		2	900	300	0.54																													R6-1R		
INT #12 US. ROUTE 5 MM. 0.005 LT	STOP	1	750	750	0.56						1			X																			R1-1		E-143
INT #12 US. ROUTE 5 MM. 0.135 LT		1	900	900	0.81						2			X																			W3-1A		E-150
INT #12 US. ROUTE 5 MM. 0.250 RT	JCT	1	525	375	0.20																													M2-1		E-135
	INTERSTATE 91	1	600	600	0.36						1			X																			M1-1		E-135
												m	m	m 40	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S 'SIGN POST DESIGN GUIDELINE.'	**TOTALS**		m² 9.32	m²	EA.	m²						m 40			m					kg			EA.					EA.	EA.	kg					

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS04.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 01/18/2006
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 130 OF 180

...\GSN\za046TS04.dgn 01/18/2006 11:06:11 AM