STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN REQUIRED FRAMED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																										
INT #12 US. ROUTE MM. 0.275 RT	HARTFORD 3 →	1	1800	300	0.54																															E-123
	← NORWICH 3	1	1800	300	0.54																															E-123
	← ST JOHNSBURY 57	1	1800	300	0.54						2			X																						E-123
INT #12 US. ROUTE 5 MM. 0.313 LT	SOUTH	1	600	300	0.18																													M3-3		E-135
	INTERSTATE 91	1	600	600	0.36																													M1-1		E-135
	←	1	525	375	0.20						1			X																				M6-1		E-135
INT #12 US. ROUTE 5 MM. 0.315 RT	NORTH	1	600	300	0.18																													M3-1		E-135
	INTERSTATE 91	1	600	600	0.36																													M1-1		E-135
	↰	1	525	375	0.20						1			X																				M5-1L		E-135
INT #12 US. ROUTE 5 MM. 0.399 RT	NORTH TO	1 1	600 600	300 300	0.18 0.18																													M3-1 M4-5		E-135 E-136A
	INTERSTATE 91 5	1 1	600 600	600 600	0.36 0.36																													M1-1 M1-4		E-135 E-136A
	← ↑	1 1	525 525	375 375	0.20 0.20						2													2	X								X	M6-1 M6-3		E-135 E-136A
INT #12 US. ROUTE 5 MM. 0.399 LT	SOUTH	1	600	300	0.18																													M3-3		E-135
	INTERSTATE 91	1	600	600	0.36																													M1-1		E-135
	↰	1	525	375	0.20						1			X																				M5-1L		E-135
												m	m	m 20	m	m	m		EA	kg	kg	kg		kg 90.4	kg	kg	kg								
	TOTALS				m² 5.32	m²	EA.	m²				m 20			m					kg			EA. 2		kg 90.4				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS04.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 12/13/2005
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 131 OF 180