STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 3.4 (44)	3.9 (50)	5.0 (63)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 1.9 (75)	2.5 (100)	2.5 (100 MOD)	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 11.3 (75)	13.4 (89)	16.1 (100)	21.7 (125)	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAMED	REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																										
INT #13 RAMP A STA. 0+340 LT	WRONG WAY	1	900	600	0.54																														R5-1A		E-143
		1	600	600	0.36						1			X																					R9-4A		E-143
INT #13 RAMP A STA. 0+380	DO NOT ENTER	2	750	750	1.13																														R5-1		E-143
	ONE WAY	2	900	300	0.54						2			X																						R6-1L		E-142
INT #13 RAMP A MM. 0.222 RT & LT	YIELD / DO NOT ENTER	2 2	900 750	900 750	1.62 1.13						4			X																						R1-2 R5-1		E-146 E-143
INT #13 RAMP B STA. 0+030 RT	PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR RESUMERS ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES	1	900	900	0.81																														VR-046		E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	900	900	0.81						2			X																						VR-002		E-142
INT #13 RAMP B STA. 0+217 RT		1	750	750	0.81						1			X																						R3-2		E-143
INT #13 RAMP B STA. 0+233 LT	ONE WAY	1	900	300	0.27						2		X																								R6-1R		E-142
INT #13 SOUTHBOUND MM. 75.07		1	1200	1200	1.44						2			X																						W4-1R		E-150
INT #13 RAMP C STA. 0+030 RT	PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR RESUMERS ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES	1	900	900	0.81																														VR-046		E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	900	900	0.81						2			X																						VR-002		E-142
INT #13 RAMP C STA. 0+270 RT		1	750	750	0.56						1			X																						R3-2		E-143
												m	m 8.0	m 60	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg									
TOTALS					m² 11.64	m²	EA.	m²					m 68.0			m				kg			EA.		kg			EA.	EA.	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS04.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:
PLOT DATE: 01/18/2006
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 134 OF 180

...\DGN\za046TS04.dgn 01/19/2006 11:06:51 AM