STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
INT #13 RAMP C STA. 0+293 LT	ONE WAY	1	900	300	0.27						2		X																				R6-1R		E-142
INT #13 NORTHBOUND MM. 74.93		1	1200	1200	1.44						2			X																		W4-1R		E-150
INT #13 SOUTHBOUND MM. 75.16	EXIT 40 M.P.H.	1	1200	1500	1.80						2												2	X								W13-2		E-150
INT #13 RAMP D MM. 75.09		1	450	450	0.20						1	X																				OM1-1		E-150
INT #13 RAMP D MM. 75.09	EXIT 13	1	1800	1500		2.70					2												2	X										E-131
INT #13 RAMP D STA. 0+100 RT		1	900	900	0.81						2			X																		W3-3		E-152
INT #13 RAMP D STA. 0+160 RT	EAST	1	600	300	0.18																											M3-2		E-136B
	SOUTH	1	600	300	0.18																											M3-3		E-136A
	NORTH	1	600	300	0.18																											M3-1		E-136A
	VERMONT 10A	1	600	600	0.36																														E-136B
	5	1	600	600	0.36																											M1-4		E-136A
	5	1	600	600	0.36																											M1-4		E-136A
	←	1	525	375	0.20																											M6-1		E-136B
	↑	1	525	375	0.20						2												2	X							X	M6-3		E-136A
	→	1	525	375	0.20																											M6-1		E-136A
INT #13 RAMP D STA. 0+280 RT	← 1 FOOD → WRONG WAY	1	1350	185	0.25																														E-133
		1	900	600	0.54																											R5-1A		E-143
	← 1 PHONE →	1	1350	185	0.25																														E-133
	← GAS →	1	1350	185	0.25																														E-133
	← 1 LODGING →	1	1350	185	0.25																											R5-1A		E-133
	← 4 HOSPITAL	1	1350	185	0.25																														E-133
	← CAMPING	1	1350	185	0.25						2			X																					E-133
												m 2	m 8.0	m 24	m	m	m		EA	kg	kg	kg		kg 271.2	kg	kg	kg								
	TOTALS				m² 8.78	m² 2.70	EA.	m²				m 34.0			m					kg			EA. 6	kg 271.2				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS04.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 01/18/2006
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 135 OF 180

...\DATA\za046TS04.dgn 01/18/2006 11:07:07 AM